Heritage Conservation and Recreation Service	For HCRS use only
National Register of Historic Places Inventory—Nomination Form See instructions in How to Complete National Register Forms	received date entered
Type all entries—complete applicable sections	
1. Name	
historic Shockoe Valley and Tobacco Row Historic District	
and/or common N/A	
2. Location	
street & number (See Continuation Sheet # 13)	<u>N</u> // not for publication
city, town Richmond ///A vicinity of congression	Third (Thomas J. aldistrict Bliley, Jr.)
state Virginia code 51 county (in city)	code 760
3. Classification	
Category Ownership Status Present U X district public X occupied agricu building(s) private X unoccupied X comm structure both work in progress educa site Public Acquisition Accessible enterts being considered yes: restricted yeorn being considered yes: unrestricted militar	Iture X museum ercial park tional X private residence ainment religious nment scientific rial X transportation
4. Owner of Property	· · · · · · · · · · · · · · · · · · ·
name Multiple Ownership	
street & number N/A	
city, town N/Avicinity of	state N/A
5. Location of Legal Description	
courthouse, registry of deeds, etc. Richmond City Hall street & number 900 E. Broad Street	
city, town Richmond	state Virginia
6. Representation in Existing Survey	(2) (See Continuation
(1) Historic American Buildings	Sheet it 25)
title Survey has this property been det date 1934, 1936-7, 1939-40, 1969; Inventory 1957 <u>X</u> federa	ermined elegible? yes _X no
depository for survey records Library of Congress	
city, town Washington	state D. C.

7. Description Condition — excellent — good — ruins — unaltered — woved date — woved date — woved — woved — moved — moved — woved — woved

Describe the present and original (if known) physical appearance

The Shockoe Valley and Tobacco Row Historic District is roughly L-shaped and includes approximately 129 acres. It is comprised of over 500 buildings in architectural styles ranging from Federal through 20th-century industrial vernacular. Topographically the area rises gradually from the James River and Richmond Dock on the south to level out along E. Main and E. Franklin streets. On the northeast, Church and Union hills present a steep ascent. The area between 14th and 19th streets encompasses the Shockoe Creek flood plain which continues north along the route of the creek. (The creek is now covered over.)

The original town of Richmond was laid out in a grid system by Maj. William Mayo in 1737 between 17th and 25th streets, E. Cary and E. Broad streets. Subsequent annexations in 1769, 1780, 1793, and 1810 added 2.20 square miles to the town and extended the grid plan. The most obvious divergence from the grid results from Shockoe Creek's interruption of 16th Street.

The boundaries of the historic district were determined by the above-mentioned geograph by virtue of three previously designated National Register districts (Shockoe Slip Historic District, St. John's Church Historic District (also known as Church Hill), and the James River and Kanawha Canal Historic District), and by the existing architectural character of the area. The southwest boundary, the Seaboard Coast Line tracks from Dock Street to Creek Alley, lies in close proximity to the Shockoe Slip Historic District. Plans call for the enlargement of the Shockoe Slip district to abut the Shockoe Valley and Tobacco Row Historic District. The land north of Lombardy Alley, just west of the district, was one the site of numerous 19th-century commercial and cultural buildings; within the past twenty-five years, however, the entire area was demolished and rebuilt. Today it is dominated by state office buildings, parking lots, and the Richmond-Petersburg Turnpike.

Although the eastern side of the 00 block of N. 15th Street is now a parking lot traversed by the elevated Richmond-Petersburg Turnpike, it has been included within the district for historical reasons. Bell Tavern, a popular late 18th-century hostelry, was located here; and, in the early 19th century, N. 15th Street was laid out through the property. Later the St. Charles Hotel (Built 1846, demolished 1903) stood on the site and was operated as Confederate General Hospital #8 from 1861 to 1863. Most recently used as a parking lot for Main Street Station, the lot is fronted by a massive coursed-ashlar wall continuous with the formal Main Street Station entrance. North 16th Street, a 19th-century, spall-block road and now a short block between E. Broad and E. Marshall streets, is the only open section of 16th Street remaining within the district.

The northeast corner is the district's weakest boundary due to large-scale demolition within the past five years. The northern edge (400 block of N. 18th Street) borders on the base of Union Hill and Jefferson Park. It includes the entrance to the Church Hill railroad tunnel (1872, closed 1926) and provides a strong geographic terminus. The section to the immediate south and east, however, is now vacant land except for a well-defined grouping of 19th-century structures contiguous to the 200 and 300 blocks of N. 19th Street. To the east of this enclave, there is vacant land or buildings of nominal architectural quality.

8. Significance

Period prehistoric 1400-1499 1500-1599 1600-1699X 1700-1799X 1800-1899X 1900-	Areas of Significance—C archeology-prehistoric x agriculture x architecture art x commerce communications		landscape architectur lawX literature _X military music : philosophy _X politics/government	e religion science sculpture social/ humanitarian theater transportation other (specify)
Specific dates	N/A	Builder/Architect	N/A	

Statement of Significance (in one paragraph)

STATEMENT OF SIGNIFICANCE

Named for the creek that once served as the western boundary of Richmond's original town settlement and for the imposing row of tobacco warehouses that once constituted its industrial core, the Shockoe Valley and Tobacco Row Historic District encompasses the area of Richmond's earliest residential, commercial, and manufacturing activity. Founded by Col. William Byrd in 1737 and incorporated as a town in 1743, Richmond on the James arose in the third quarter of the 18th century as a natural marketplace for the commerce of the Middle Piedmont. The designation of the town as the capital of Virginia in 1779 and the subsequent improvement of its canal and railroad transportation system in the antebellum period largely explain Richmond's emergence by 1860 as one of the leading commercial cities in the South and the major tobacco manufacturing center in the nation. The city played a unique role in the Civil War, serving not only as the Confederate capital, but also as the chief manufacturer for the Southern war effort. Despite defeat and the ravages of war, Richmond experienced a surprisingly rapid economic recovery in the postbellum period, attributable mainly to the resurgence of its tobacco industry. Besides its integral part in Richmond's growth and survival as a commercial and industrial city, the Shockoe Valley and Tobacco Row Historic District is significant for the stylistic diversity of its approximately 530 residential, commercial, and industrial buildings. Associated with such important themes as economy, trade, transportation, government, literature, and architecture, the district is thus representative of the major stages of Richmond's evolution from village to metropolis,

HISTORICAL BACKGROUND

Richmond was originally settled in the area known as the Falls, the western boundary for the tidal James. Two of the first attempts at settlement in the region were undertaken in 1609 by Capt. Francis West and Capt. John Smith. Captain West established a small community at the edge of the James River, while Captain Smith moved slightly inland. The latter purchased his land from the Indian Chief Little Powhatan in exchange for some copper and named the settlement Fort Powhatan. Because there was "no place so strong, so pleasant, and delightful in Virginia," Captain Smith changed the name to None Such. Both settlements were soon abandoned because of the rivalry between West and Smith and because of ongoing conflicts with the Indians. A later attempt to settle this area occurred in 1679 when William Byrd I, arriving from England with fifty men, successfully planted a settlement in the vicinity of the Falls as a barrier between the frontier and the Indians. Then, in 1733, Col. William Byrd II "conceived the plan of (formally) laying out his lands for a town." Byrd's journal entry of 1733 states:

When we got home we laid the foundation of two large cities, one at Shacco's, to be called Richmond, and the other at the falls of the Appomattox River, to be named Petersburgh. These Major Mayo offered to lay out into lots without fee or reward. The truth of it is, these two places being the uppermost landing of James and Appomattox Rivers,

	· ·
9. Major Bibliographical F	References
University Studies in Historical and P Berman, Myron. Richmond's Jewry, 1769-1976	try in Virginia from 1860-1894." Johns Hopkins Political Science. I-II (JanFeb., 1897). 9-86. Shabbat in Shockoe. Charlottesville: Univer Continuation Sheet #12)
10. Geographical Data	
Acreage of nominated property 129 acres Quadrangte name Richmond, Va. UMT References	Quadrangle scale 1:24000
A 1 8 2 8 5 9 0 0 4 1 5 6 9 9 0 Northing	B 1 8 2 8 6 2 6 0 4 1 5 5 9 7 0 Zone Easting Northing
c 1 8 2 8 6 2 6 0 4 1 5 5 8 1 0	$D[1_18]$ $[2]8_16[1_16_10]$ $[4_11[5_15]7_13_10]$

12 | 8 | 5 | 2 , 2 , 0 |

(See Continuation Sheet #13)

List all states and counties for properties overlapping state or county boundaries

state ///A code county ///A code

state ///A code county ///A code

11. Form Prepared By

14 1 5 7 0 1 0 1

G | 1 | 8 | | 2 | 8 | 5 | 4 | 2 | 0 |

Verbal boundary description and justification

Virginia Historic Landmarks Commission Staff; Karen Lang-Kummer and A. Rebecca name/title Harrison, 1980 Summer Interns April 1981 Virginia Historic Landmarks Commission organization date (804) 786-3144 221 Governor Street street & number telephone 23219 Virginia Richmond city or town state


12. State Historic Preservation Officer Certification

	· Otaly iii	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,		<u> </u>	<u> </u>	, , , , , , , ,	,
The c	evaluated significance of	this property within	the state is:	•		· · · ·	
	national	<u>X</u> state	local				
65), scco	e designated State Histor I hereby nominate this portion of the criteria and por	operty for inclusion rocedures set forth (in the National R by the Heritage C	egister and certify	y that it i Recreation	has been evalu	
itle	Tucker Hill, Exec	utive Director	7	· judice	date	MAY 10	1982
For	HCRS use only with the line of	and selections	nessentar viel etilbers				

National Register of Historic Places Inventory—Nomination Form

Shockoe Valley and Tobacco Row Historic District, Richmond, VA

Continuation sheet #1 Item number 7



Page :

DESCRIPTION

From the 100 block of N. 21st Street east, the district tapers south to Peach Street, following the geographical base of Church Hill and the southern boundary of the St. John's Church Historic District. Peach Street marks the narrow eastern end of the Shockoe Valley and Tobacco Row Historic District. Beyond this street, the land begins to fan outward forming the Rocketts and Fulton areas of Richmond. The northern boundary of the James River and Kanawha Canal Historic District, from the Great Ship Lock to the Seaboard Coast Line railroad tracks, forms the southern boundary of the Shockoe Valley district.

Historically this area had a high concentration of residential property consisting of either single-family dwellings or flats situated above first-floor shops. Present land use, however, is primarily confined to commercial and industrial activity. The only remaining residential neighborhood is centered around the 200 block of N. 19th Street and contains late 18th-through late 19th-century town houses. This area has become the nucleus of the City of Richmond's Shockoe Valley Old and Historic District. Only limited use is presently being made of flats located above commercial establishments.

Industry is concentrated south of E. Main Street, particularly along E. Cary Street. Here large tobacco manufacturing and warehouse complexes dominate to such an extent that this area is termed "Tobacco Row". The proximity of the Richmond Dock and canal and, later, the railroad lines led to the early industrial development of this section and its continued use. Additional light and heavy industry is randomly scattered through the district with minor clusters north of E. Broad Street and east of N. 18th Street.


Commercial activity is primarily focused on the 17th Street Farmers' Market and the area bounded by the Market, E. Main, E. Franklin, and N. 18th streets. The 1700 block of E. Main Street is flanked by a continuous facade of late 19th- and early 20th-century mercantile buildings. East Franklin Street has a variety of buildings including modified Greek Revival shops, 19th-century stables, and early 20th-century structures, the latter buildings primarily housing wholesale fish and produce businesses. North 17th and 18th streets contain a mixture of wholesale and retail establishments analogous to those of E. Main and E. Franklin streets. Most buildings in this area are of masonry construction, ranging from one to three stories in height.

The old Henrico County Courthouse and Sheriff's Office (2127 and 2117 E. Main Street) now house the Henrico Department of Parks and Recreation and are the only governmental faciliti operating within the district. Engine Company #2 (2016 E. Main Street) and Truck Company #2 (1805 E. Grace Street) fire stations are extant but have been converted to private ownership. No functioning religious structures remain, although a Jewish cemetery (2009 E. Franklin Street a Methodist Sunday School building (104 N. 18th Street), and a Jewish temple (209 N. 19th Stree still exist.

In spite of being in constant use and change since the mid-18th century, Shockoe Valley and Tobacco Row still present a variety of architectural styles including late 18th-century and Federal vernacular, Greek Revival, Italianate, Second Empire, Romanesque Revival, Classical Revival, Colonial Revival, and late 19th- and early 20th-century commercial and industrial vernacular. The oldest, and only stone, building remaining in the district is the Old Stone House (1916 E. Main Street; NRHP). Reputed to date from 1737, it now houses memorabilia relating to Edgar Allan Poe's life in Richmond. Early Federal architecture is represented

the second secon

National Register of Historic Places Inventory—Nomination Form



Page 2

DESCRIPTION

in the frame Adam Craig House (1812 E. Grace Street; 1784-1787) and Masons' Hall (1805 E. Franklin Street; 1785-1787; NRHP).

There are a number of fine examples of Greek Revival houses clustered within the one remaining residential section. These include Elm Tree Row, a contiguous grouping of three double town houses (301-303, 305-307, 309-311 N. 19th Street; 1853), the Crump Double House (1813-1815 E. Grace Street; 1818), the Lacy Houses (211 & 213 N. 18th Street; 1850), and the Greaner House (232 N. 20th Street; 1858). Scattered throughout the area are other Greek Revival buildings which have been altered for modern commercial use. Prominent examples are 1708 and 1710 E. Franklin Street (1842); 1800-1810 E. Main Street (ca. 1840); and 3, 23-27, and 22-24 N. 17th Street (1833, 1853, 1840). The latter three buildings flank the Farmers' Market and give evidence of the early character of the market area.

Numerous commercial Italianate buildings are located within the district, many of which have had their first floors altered. 2215-2219 E. Main Street (ca. 1870) and 101-109 N. 18th Street (Belle Bossieux; 1878) retain their storefronts, while 15 and 29 N. 17th Street (ca. 1885, ca. 1875) display excellent Italianate detailing above the first floor. A noteworthy Italianate mansion is the Pace-King House (205 N. 19th Street; 1860; NRHP), known for its elaborate cast-iron veranda. Within the same block are later vernacular Italianate houses.

Examples of other late 19th-century architectural styles occur within the district but are not prevalent. These rare examples of Second Empire (219 N. 19th Street; remodeled ca. 1870), Romanesque Revival (2127 E. Main Street; 1896), and Colonial Revival (2117 E. Main Street; 1892) add distinct points of interest to the district.

Contributing to the general character of the area, the dominant commercial and industrial architecture reflects a wide range of 19th- and 20th-century tastes. Cast-iron storefronts are found throughout the district, particularly along E. Main Street. 1701 and 1720-1726 E. Main Street have manufacturing company plaques on the cast-iron pilasters. Another prominent feature, often used in combination with cast-iron storefronts, is decorative brickwork. 1557 E. Main Street (ca. 1890) is a notable example as are 2500 E. Cary Street and 1709 E. Clay Street. Many buildings reveal traces of painted advertising signs along their front and side elevations. Examples can be seen at 29 N. 17th Street, 423 N. 18th Street, 2424 E. Main Street, and 1617 E. Franklin Street.

Industrial architecture ranges from antebellum tobacco factories located north of E. Main Street to large Art Deco warehouses along E. Cary Street. Two early 20th-century warehouses at E. Cary and S. 18th streets are exceptionally sophisticated examples of brick industrial architecture. Of particular interest are the series of late 19th-century brick warehouses along Tobacco Row: Cardwell Machine Co. (1900 E. Cary; 1893), Climax Warehouse (2010 E. Cary; 1899), P. Lorillard Co. Warehouse (11 S. 23rd; ca. 1890), and Kinney Warehouse (2500 E. Cary; 1886). The area north of E. Broad Street also has a collection of significant industrial buildings including two freight depots (300 & 400 N. 17th Street), the old Armour abattoir (307 N. 17th Street), and a cold storage complex (1711-1713 E. Clay Street).

Closely allied with the industrial activity of the district are the transportation networks of canal and railroad. The James River and Kanawha Canal, a National Register historic


National Register of Historic Places Inventory—Nomination Form

Shockoe Valley and Tobacco Row Historic District, Richmond, VA

Continuation sheet #3

Item number

er 7



Page 3

7. DESCRIPTION

district, began in the Shockoe Valley area in 1816 as the Richmond Dock Company. The present granite ship locks at the eastern terminus date from 1854 and are the center of a small city park. Situated below Tobacco Row, the Richmond Dock serves as a constant reminder of the role the canal system played in the district's early business activities.

Main Street Station, a magnificent Second Renaissance Revival National Historic Landmark, serves as a visual anchor for the vast network of railroad tracks which cross the area. Two viaducts (ca. 1900) of the Seaboard Coast Line and Chesapeake and Ohio railroads follow the route of Shockoe Creek⁴ south to the steel-truss train shed at the rear (north) of Main Street Station. At this point the Seaboard Coast Line viaduct crosses the James River while the Chesapeake and Ohio river viaduct turns east to continue along the south side of Dock Street. A second complex of railroad tracks (Chesapeake and Ohio) is located north of E. Broad Street and is centered around the two freight depots at 300 and 400 N. 17th Street. A Seaboard Coast Line freight depot stands to the northwest of Main Street Station. Other notable railroad engineering works include wood coal trestles (located to the rear of 1604 E. Broad Street) and the old Church Hill tunnel.

Land densities and lot sizes vary across the district. Although early Richmond was compactly built, only the sections near the Farmers' Market and along Tobacco Row continue this quality. Here buildings are generally of two through five stories in height with no setback from the street. Much of the remaining area has been compromised by a loss of buildings. The resulting one-story infill, vacant land, and parking lots detract from the district's visual integrity. East Broad Street, Dock Street, and the eastern portion of E. Main Street are weak in this regard. The 1958 Richmond-Petersburg Turnpike and its 1977 Downtown Expressway connection, which are located between N. 15th and S. 17th streets, resulted in a large amount of open land beneath the elevated roadway and visually impair the quality of the district in this area.


Vestiges of 19th-century, spall-block paving remain on many of the lesser-traveled streets and alleys. Examples include Crane Street, N. 16th and N. 26th streets, and the Bossieux, Walnut, Whitlock, and Pace alleys. Two streets are paved in brick (S. 21st, and S. 22nd), while a majority of the sidewalks throughout the district have remnants of brick patterns. Most streets within the district provide for two-way vehicular traffic and on-street parallel parking. Heaviest traffic appears centered on E. Main Street and E. Broad Street, major east-west arteries, and 17th Street. State highways #5 and #33 and U.S. highways #60 and #250 traverse the area.

Although the Shockoe Valley and Tobacco Row Historic District displays an amazing array of architectural styles, many buildings are in a state of disrepair. Throughout the district vacant land and parking lots exist where 19th-century buildings have been lost through deterioration, neglect, and vandalism. Recent construction not compatible with the scale, massing, or texture of the area has led to some loss of historic integrity. However, efforts to revitalize the Farmers' Market area and Tobacco Row are attempting to reverse this trend. The Shockoe Bottom Farmers and Merchants Association was organized in June 1980 to promote commercial activity within the district and currently has over 130 members. In addition, Main Street Station is undergoing study for conversion into a shopping mall complex, while a number of the large tobacco warehouses have been proposed for condominium use. Non-profit enterprises include

National Register of Historic Places Inventory—Nomination Form

Shockoe Valley and Tobacco Row Historic District, Richmond, VA

Continuation sheet #4 Item number 7,8



Page 4,1

7. DESCRIPTION

the restoration of the Pace-King House by the Association for the Preservation of Virginia Antiquities and the exterior renovation of the Belle Bossieux by Historic Richmond Foundation. These efforts in conjunction with expressed support by the city and private concerns have led to renewed interest in this area.

Karen Lang-Kummer

1The Shockoe Valley Old and Historic District was created by the Richmond City Council on February 14, 1977, and enlarged on October 23, 1978. The boundaries are roughly N. 18th Street between E. Franklin and E. Broad streets on the west, E. Broad Street and Elm Tree Row (300 block of N. 19th Street) on the north, the alley between N. 19th and 20th streets and the west side of N. 19th Street on the east, and E. Franklin Street on the south.

 2 Large stone walls are located at 1500 E. Main Street and on the 26th Street elevation of 17 S. 25th Street.

³1701 E. Main Street (ca. 1910) has pilasters marked "Asa Snyder and Co., Richmond Va.". The Asa Snyder and Co. Architectural Iron Works was established in 1871 at 1008-12 Cary Street 1720-1726 E. Main Street (1914) ironwork was manufactured by the Cardwell Machine Co. located at 1900 E. Cary Street.

⁴Shockoe Creek's meandering course was straightened throughout the 19th century. During the 1920s it was contained underground in a box and arch sewer system designed to carry the steel railroad viaducts.

⁵Many of the alleys within the district have historic names. Most of the names were designated in 1819. See the Council Minutes, Vol. 7, Aug. 16, 1819, p. 22.


8. SIGNIFICANCE

are naturally intended for marts, where the traffick of the outer inhabitants must centre. Thus we did not build castles only, but also cities, in the air.⁵

The original town, located between today's 17th and 25th streets and E. Broad and E. Cary streets, was laid out in a grid by Maj. William Mayo in April 1737. A total of thirty-two squares was laid out -- four squares wide and eight long, each square containing four lots. The row of squares farthest west, designated by letters instead of numbers (refer to illustration A), was originally intended for villas. The area was named Shockoe after the creek that formed the western boundary of the original settlement. The derivation of the name of the creek itself is not known. On May 15, 1742, Richmond was incorporated as a town having approximately 250 inhabitants. Most subsequent expansions of Mayo's plan took place to the west, as the steep bank of Church Hill proved to be a formidable barrier.

National Register of Historic Places Inventory—Nomination Form

Shockoe Valley and Tobacco Row Historic District, Richmond, VA Continuation sheet # 5 | Item number 8



Page 2

3. SIGNIFICANCE

Shockoe Valley's long association with the Henrico County court began with the removal of that county's seat from Varina to Richmond in 1752. The 1752 Henrico courthouse, constructed in the middle of what was later to become 22nd Street, just south of E (now Main) Street, was probably the earliest public building in the neighborhood, then known as "Bird in Hand," after the tavern of the same name located at 25th and E (Main) streets. A pillory, whipping post, and stock were soon erected at the public marketplace at E (Main) and 17th streets, while a ducking stool, "only for women of unruly tongue," was constructed on Shockoe Creek. 8

Richmond's regional status changed radically in 1779 when the decision was made to move the capital there from Williamsburg. Affording greater protection from the danger of British invasion, the city was chosen because it was "more safe and central than any other town situated on navigable water." Although the original capitol was located on the west side of 14th Street, outside the boundaries of the district, it had great influence on the growth and development of Shockoe Valley. Appointment as the new state capital precipitated Richmond's incorporation as a city in 1782 and caused the Henrico Courthouse to be pressed into service as the court of the Richmond Hustings Court and the Virginia Supreme Court of Appeals. Among the most important patrons of the Valley's growing number of shops and taverns would be the host of delegates and senators who came each winter to Richmond for the annual convention of the legislature.

A second catalyst to Richmond's early growth was the development of its canal and rail-road transportation system. The James River and Kanawha Canal, located just south of the Shockoe Valley and Tobacco Row district, was conceived by George Washington as part of a larger system of canals which would ultimately reach the Ohio River. 10 The Richmond Dock and locks (set aside now as the Great Ship Lock Park) were part of this canal project begun in 1816 to aid in James River navigation from the wharves past the falls. 11 Once extending south of Dock Street between 14th and 23rd streets, the dock today extends from 17th to Pear streets.

Navigation between Richmond and Lynchburg was opened up in 1840, and eleven years later the canal reached its westernmost point at Buchanan. The canals provided employment opportunities, facilitated trade, and encouraged the movement of people to and from Richmond. Canal use peaked between 1844 and 1854. Much of the tobacco manufacturing in antebellum Virginia coincided with the age of canal building. The James River and Kanawha Canal provided a vital link between the Piedmont farms and the markets at Richmond and allowed the city to grow into the leading commercial tobacco center in Virginia. Until 1850 transportation of tobacco by rail served only to supplement the activity of bateaux carrying hogsheads to market by water.

After 1854 the railroad supplanted the canal as the primary commercial transportation system in Richmond. The first rail line to serve Richmond, the Richmond, Fredericksburg, and Potomac Railroad, began operating in 1836. Other lines opened in rapid succession: the Richmond-Louisa Railroad (1837), the Richmond and Petersburg Railroad (1838), an extension to the Richmond, Fredericksburg, and Potomac line from Fredericksburg to Aquia Creek (1842), and the Richmond and Lynchburg Railroad (1860).

In the first half of the 19th century, the Piedmont plateau, including Richmond, Lynchburg, and Petersburg, served as the tobacco manufacturing center of the south. Seventy percent of all tobacco inspection was centered in the counties containing these towns. 12 Richmond's

National Register of Historic Places Inventory—Nomination Form

Shockoe Valley and Tobacco Row Historic District, Richmond, VA

Continuation sheet #6 Item number 8



Page :

SIGNIFICANCE

tobacco manufacturing was concentrated in the Valley along what has been known historically as Tobacco Row. The first city directory, published in 1819, lists eleven tobacco factories. 13 During the 1830s and 1840s, tobacco manufacturing boomed in Richmond. As companies grew, larger productive units were merged with smaller ones, resulting in a notable increase in warehouse size. An 1837 article in the Richmond Whig and Public Advisor describes Shockoe, Public, and Seabrook's warehouses of Richmond (perhaps with some exaggeration) as covering about 2½, 1½, and one acre respectively. These warehouses were so spacious that they were occasionally used for public gatherings.

Five new factories were under construction in September 1852. Three years later the city directory listed forty-one separate factories, and in late 1858 a survey showed fifty-three chewing tobacco factories. By 1860 Richmond was clearly the tobacco manufacturing center of the nation. Two indications of growth were the institution of the Richmond Tobacco Exchange in 1858, which centralized the marketing of leaf tobacco, and the opening of consulates in Richmond by France, Austria, Belgium, and Brazil. 16

The 1860 Census listed fifty-five factories in Richmond. Major ones in the Shockoe Valley and Tobacco Row district were Mayo's factory, a supplier of quid tobacco to the Navy; Myers Brothers, which exceeded all other Virginia and North Carolina factories in quantity in 1850; John Enders (20-26 N. 20th Street; ca. 1849); William Grant (1900 E. Franklin; 1853); and the Robinson Factory, which was the fourth largest tobacco manufacturer in the city (2020 E. Franklin Street; 1854).

In addition to its substantial tobacco interests, Richmond served as an important regional mercantile and trading center before the Civil War. According to historian Mary Wingfield Scott, Richmond possessed a public marketplace as early as the 1780s. Provisions for establishing such a market were included in a General Assembly act of 1780 "...for locating the public squares, to enlarge the town and for other purposes." In addition to designating sites for the capitol, halls of justice, state houses, etc., the Assembly established a public market on a site "below the hill on the same side of the creek." This place is now known as the First, Old, or Farmers' Market located on N. 17th Street between E. Main and E. Grace streets. The original structure was a wooden shed supported on locust posts. 19 In 1794 it was replaced by a brick building, the second floor of Which was used as a theatre. Eighteen years later, it was rearranged to house the courtroom for the Hustings Court. 20 The city and the Adams and Byrd heirs (the original owners of the land) entered into an agreement in 1818 to extend the market north towards E. Grace Street. Due to the market's popularity, a large structure was erected in 1854 and stood until 1913.

Besides the public marketplace, numerous shops, hotels, and taverns once flourished in the Valley. Although none of the following establishments stands today, each was a familiar landmark to Richmonders in the antebellum period: the Bird-in-Hand (site at 25th and E. Main streets; ca. 1750), the United States Hotel (site at 19th and E. Main streets; 1817), and the Bell Tavern, a favorite meeting place for state legislators, which was located at 15th and E. Main streets in 1812.

Shockoe Valley also provided the setting for the work of Richmond's most famous literary figure in the antebellum period, Edgar Allan Poe. Orphaned when he was about three years old,

National Register of Historic Places Inventory—Nomination Form

Shockoe Valley and Tobacco Row Historic District, Richmond, VA Continuation sheet #7 Item number 8



Page 4

B. SIGNIFICANCE

Poe grew up in Richmond, reared by a Shockoe Valley tobacco merchant, John Allan, whose name he later adopted as his middle name. Poe returned to Richmond in 1835 to serve for two years as assistant editor of the Southern Literary Messenger, which had its offices in the Valley at 15th and E. Main streets and then ranked first among the literary journals published in the South. One of Poe's better-known poems, "To Helen," was inspired by Jane Stith Craig, who lived with her father, Adam Craig, at 1812 E. Grace Street. Poe returned to Richmond again just before his death in Baltimore in 1849.

As the Confederate capital, Richmond became the center of intense activity during the Civil War years of 1861-1865. The city's population, just under 38,000 in 1860, increased more than twofold during the war. The eve of the war found the city at an economic apex with prosperous mills, newspapers, and commercial enterprises, as well as fifty-two tobacco factories. 21 As the city became one vast army camp, many of these enterprises halted. Rails were torn up to provide iron for the army's various needs, while hotels and industrial buildings in the district were converted for use as prisons and hospitals. A tobacco warehouse was adapted for service as the notorious Libby Prison (site between S. 20th and S. 21st streets and E. Cary and Dock streets). A warehouse on the north side of E. Cary Street between S. 18th and S. 19th streets similarly was converted into the prison called Castle Thunder. Confederate hospitals were even more prevalent in the district than prisons. Seabrook's Tobacco Warehouse, which had occupied the greater part of E. Broad and E. Grace between 17th and 18th streets, became a hospital, as did buildings on the sites of the Climax Warehouse (2010 E. Cary Street) and the Cameron Annex (2400 E. Cary Street), M.F. Neal and Company, historically known as the Grant Tobacco Factory (1900 E. Franklin Street; 1853), was also a hospital, as were the historic Robinson Factory (2020 E. Franklin Street; 1854) and the Leake Printing Company building (John Enders Tobacco Factory, 20 N. 20th Street; 1849). Except for enterprises needed to sustain the populace and the war effort, business and industry came to a standstill in spite of increased population. 22 Fire, which destroyed much of the upper city in the evacuation of 1865, touched Tobacco Row only between E. Main and E. Cary streets and S. 21st and S. 22nd streets. Other buildings lost at that time probably were torn down to make way for new construction in the postwar years.

The business community in the Valley began to revive and rebuild itself shortly after the war. The Tobacco Exchange was reestablished in 1866, and railroad companies once again began laying track. Not only were old railroad companies revived, but new ones were established, a development capped at the end of the 19th century by the construction of Main Street Station (1520 E. Main Street; 1900-1901) and the Railroad Young Men's Christian Association (1552 E. Main Street; 1907).

Tobacco was the major commodity on which Richmond was to ride to economic recovery in the postbellum era. 23 As a consequence of the war, emancipation, and heavy postwar taxes, 1860 to 1871 were years of decreasing tobacco production. 24 The key to revitalization of the industry was new investment. Among the first businessmen to risk their capital in restoring the tobacco district to life was James B. Pace, who adapted the John Greaner building at 9-11 N. 22nd Street for use as a factory. The great tobacco revival occurred between 1871 and the late 1880s. A few of the new tobacco companies emerging during this period were Hardgrove (site at Cary and Pear streets), Pace Tobacco Company (16-20 N. 22nd Street), Gregory (site at 26th and E. Main streets), and Scott and Clarke (site at 21st and E. Main streets). This new prosperity was fed by recovery from the war, lowered taxes, improved production methods, and new railroad construction.

National Register of Historic Places Inventory—Nomination Form

Shockoe Valley and Tobacco Row Historic District, Richmond, VA

Continuation sheet #8 Item number 8



Page 5

8. SIGNIFICANCE


Commerce also revived in the years following the war as new businesses were established and many shop-flat combinations were erected in the district. Among the commercial enterprises flourishing in the 1880s were confectioners; commission merchants; dealers in hides, leather, and wool; suppliers of stove and hardware items; and retail and wholesale grocers. Noteworthy buildings of this era can be seen along N. 17th Street between E. Main and E. Grace streets and on E. Main Street between 16th and 19th streets.

Symbolic of the increasing prosperity of Shockoe Valley at the end of the 19th century was the construction of the Romanesque Revival Henrico County Courthouse in 1896. Combining a distinctive mixture of architectural details and styles, the building was fashionably Victorian, representing the best architecture of the period. As the third Henrico courthouse to stand at the intersection of 22nd and Main streets, it also maintained the Valley's long association with this important institution of local government.

Unfortunately for the Tobacco Row area, the arrival of the 20th century brought with it a decline in the number of locally owned factories within the district. The causes of this development were largely twofold. Other states, notably North Carolina, began competing for the leadership position in the manufacture of tobacco products. The 1893 financial panic caused smaller businesses in the district either to fold or to sell out to the larger tobacco concerns. This decline among small manufacturers also resulted from increased automation in production as well as aggressive marketing techniques which could only be afforded by the larger companies. In 1890 the largest of the Richmond manufacturers, Allen and Ginter, merged with W. Duke and Sons, Kinney Tobacco Company, W. S. Kimball and Company, and Goodwin and Company to form the huge American Tobacco Company, which soon controlled 90 percent of the cigarette manufacturing in the country. 26 A further merger in 1904 resulted in the formation of a new American Tobacco Company with a near monopoly on both the cigarette and plug tobacco manufacture. The manufacture of tobacco products continued to thrive in the Valley with the construction of the Cameron Annex (2400 E. Cary Street; 1897, 1905) and the Climax Warehouse (2010 E. Cary Street; 1899), but their construction marked the end of the era of independent manufacturing in the Valley. One of the only independent companies to see expansion in the early 20th century was Larus and Brother Company, Inc. Established in 1877 by Charles Dunning Larus on E. Franklin Street, the company expanded into new quarters on S. 21st Street in 1897. In 1911 following a large fire, a new facility was constructed, with substantial additions in 1916 and 1925. These plants manufactured tobacco products, most notably Edgeworth Pipe Tobacco, until the mid-20th century. 27 Even though tobacco manufacturing in Shockoe Valley is of less importance today than it was in the 19th and early 20th centuries, large conglomerates such as Philip Morris (established in 1933, 20th and E. Cary streets) and American Tobacco (21st and E. Grace streets) still employ many of the old factories and warehouses that date from the early years of the present century.

The decline of the residential area of the district in the 20th century had its roots in a much earlier period. The original core of Richmond had been slowly abandoned as the city expanded to the west. The erection of the State Capitol on Council Chamber Hill early symbolized this westward shift, which transformed the character of Shockoe Valley from an area that combined residential, governmental, mercantile, and industrial activity to one in which commerce and industry predominated. The district accordingly became less attractive as a place of residence, as fashion dictated a more convenient location on the hill surrounding the capitol.

National Register of Historic Places Inventory—Nomination Form



Page 6

8. SIGNIFICANCE

Decreasing traffic on Richmond railroads and streetcars was another factor in the decline of the Valley, with passenger and street railroad systems competing less and less successfully with the automotive and trucking industry in the first half of the 20th century. By 1976, the Main Street Station and the Railroad YMCA, as well as the subsidiary businesses catering to railroad passengers, were obsolete. Highways such as the Downtown Expressway and the Richmond-Petersburg Turnpike (sections of which were constructed in the 1960s) directed much of the local traffic to other areas, depriving the Valley of yet another important commercial catalyst. With the diminishing contribution of Tobacco Row to the manufacture of tobacco products in the city, buildings fell into a state of disuse and disrepair, inviting demolition and accelerating the deterioration of the area.

Flooding caused by hurricanes Camille (1969) and Agnes (1972) resulted in extensive damage to many of the businesses that had survived a half century of economic adversity. When the high waters receded, many Valley residents elected not to return to the district. Similarly, many owners of water-damaged buildings chose not to repair them, either because customers were moving away or because the financial burdens proved unbearable.

Despite the intrusion of demolition and a general state of depression in the district, an excellent array of historical buildings still attests to Shockoe Valley and Tobacco Row's unusually rich history. Virtually all styles of architecture popular in the United States from the late 18th century to 1925 are represented within the district's boundaries. These styles include late 18th-century and Federal vernacular, Greek Revival, Italianate, Second Empire, Romanesque Revival, Classical Revival, Colonial Revival, and commercial industrial vernacular.

Richmond's oldest house is in the district at 1916 E. Main Street (NRHP), purportedly dating from 1737. Having been the longtime family residence of the Ege family, it now constitutes part of the Edgar Allan Poe Museum. Examples of Federal architecture are the Adam Craig House (1812 E. Grace Street; 1784-87) and the Masons' Hall (1805 E. Franklin Street; 1785-87; NRHP). Worthy of particular recognition, the Masons' Hall is the oldest building in the United States to have been erected as a Masonic Hall and to have been continually used for that purpose.

The best examples of Greek Revival architecture are all within a two-block radius between N. 18th and N. 20th streets and E. Grace and E. Marshall streets. They are Elm Tree Row (301-03, 305-07, 309-11 N. 19th Street; ca. 1853), the Lacy Houses (211 and 213 N. 18th Street; ca. 1850), the Greaner House (232 N. 20th Street; ca. 1858), and the Crump Double House (1813-15 E. Grace Street; ca. 1818). Other buildings of the same style, but in various states of repair and preservation, are scattered throughout the district, including a few along the Old Farmers' Market (3, 23-27, 22-24 N. 17th Street; ca. 1833, 1853, and 1840, respectively).

The Pace-King House (205 N. 19th Street; ca. 1860; NRHP) is an excellent example of residential Italianate architecture. Its elaborate iron veranda is a manifestation of Richmond's famous ironwork. Commercial Italianate buildings, some with altered storefronts, are prevalent. 15 and 29 N. 17th Street (1885, 1875) have exemplary Italianate details above remodeled storefronts, while 2215-19 E. Main Street (ca. 1870) and Belle Bossieux (101-109 N. 18th Street; ca. 1878) have original first-floor facades. 28

National Register of Historic Places Inventory—Nomination Form

Shockoe Valley and Tobacco Row Historic District, Richmond, VA

Continuation sheet #10 Item number 8



Page 7

8. SIGNIFICANCE

The district also boasts one example each of Second Empire, Romanesque Revival, and Colonial Revival styles. These examples are found at 219 N. 19th Street (ca. 1870 remodeling), 2127 E. Main Street (Henrico County Courthouse; 1896), and 2117 E. Main Street (ca. 1892), respectively.

The predominantly commercial and industrial character of the district is reflected in the buildings that display various 19th- and early 20th-century styles. Cast-iron storefronts, a familiar feature of the Shockoe Slip area of Richmond, can also be found in the Valley. These facades, in conjunction with the iron veranda of the Pace-King House (205 N. 19th Street; ca. 1860; NRHP) and ironwork on the north side of 29 N. 17th Street, are indicators of Richmond's prosperous mid-19th-century iron manufacturing industry. Other examples are found on E. Main Street. Decorative brickwork is found on many commercial buildings including 1557 E. Main Street and 1705 E. Main Street. Old signs similarly add to the character and uniqueness of some of the district's buildings. 1 N. 19th Street, 29 N. 17th Street, and 423 N. 18th Street feature an interesting exhibition of painted signs and advertising.

Architecturally, the 19th- and early 20th-century commercial scale of two and three stories has been preserved in the district, most notably on E. Main, E. Franklin, N. 17th, and N. 18th streets. The Old Farmers' Market, rebuilt for the fourth time in the late 1940s, continues to function at the traditional 17th Street location under an aluminum and steel shed. Many buildings in the area still house fish markets and produce stands (Butcher's at 15 N. 17th Street, Snead's at 101 N. 17th Street, and Loving Produce located at 1600 E. Franklin Street).

Fine examples of late 19th- and early 20th-century industrial vernacular buildings stand all along Tobacco Row on E. Cary Street. Notable examples are 1712 E. Cary Street (ca. 1920), 1717-21 E. Cary Street (1914), and 2010 E. Cary Street (1899). Art Deco-influenced warehouses similar to those at 2600-16 E. Cary and S. 20th streets are scattered throughout the district as well as antebellum factories (20-26 N. 20th Street, ca. 1849; 1900 E. Franklin, 1853; and 15-23 N. 19th Street). The early 20th-century factories located north of E. Broad Street between N. 17th and N. 18th streets are also worthy of recognition.

In addition to its variety of architectural forms, the district exhibits traces of the cultural diversity of early Richmond. In the last decade of the 18th century, the Jewish population of Richmond was exceeded only by that of New York, Charleston, and Philadelphia. The first Jewish businesses in Richmond were located in the Valley, most notably the Bird-in-Hand, which was the oldest tavern in the city. Only two reminders of this heritage still remain in Shockoe — the old Temple Kenesseth Israel and the Jewish cemetery of 1791. The temple, located at 209 N. 19th Street and built in 1908, was a Polish synagogue whose congregation was established here in the 19th century. The cemetery (2009 E. Franklin Street), established by Isaiah Isaacs, was abandoned in 1817, after which year it was used as a coal yard and junkyard. It was restored and reconsecrated in 1909.


In the last several years, efforts to preserve and restore the historic fabric of Shockoe Valley and Tobacco Row have increased. The Shockoe Bottom Farmers and Merchants Association

National Register of Historic Places Inventory—Nomination Form

Shockoe Valley and Tobacco Row Historic District, Richmond, VA

Continuation sheet #11

L Item number 8



Page 8

8. SIGNIFICANCE

has been established to promote the rehabilitation of the district, which remains the whole-sale food marketing center of Richmond. S.W.A. Partnership of Richmond has announced plans for an elaborate restoration of Main Street Station, and local shop owners are already working to restore some of the buildings around the Old Farmers' Market (13, 109, and 111 N. 17th Street and 1702 E. Main Street). Other businessmen have expressed a sincere interest in renewing the area and could greatly benefit from the federal tax incentives for rehabilitation. Residents of the district are no less receptive to the idea of restoring the character and traditions of the community. A final note of encouragement to preserving Shockoe Valley and Tobacco Row Historic District is the Army Corps of Engineers's recent consideration of a proposal to erect a flood wall along the James River from 12th Street to 23rd Street. Although deteriorated sections exist in the district and many noteworthy buildings have been lost over time, the approximately 530 structures that do survive maintain the essential historic fabric of early Richmond and its industrial years.

A. Rebecca Harrison

lyirginius Dabney, Richmond: The Story of a City (New York: Doubleday & Co., Inc., 1976), p. 4.

²Mary Newton Stanard, Richmond: Its People and Its Story (Philadelphia & London: J. B. Lippincott Co., 1923), p. 7.

³James K. Sanford, ed., <u>Richmond: Her Triumphs, Tragedies and Growth</u> (Richmond: Richmond Chamber of Commerce, 1975), p. 10.

⁴Ibid.

⁵Louis Wright, ed., The Prose Works of William Byrd of Westover (Cambridge: Belknap Press of Harvard University Press, 1966), p. 388.

⁶Sanford, p. 10.

⁷William W. Hening, <u>The Statutes at Large: Being a Collection of all the Laws of Virginia</u>, Vol. 5, Chapter 20, 1742, pp. 191-193.

⁸John O. and Margaret T. Peters, Courts of the Richmond Area - A Primer (Richmond: Bar Association of the City of Richmond, 1969), pp. 27-31.

⁹Sanford, p. 18.

¹⁰Dabney, p. 46.

llDavid LaPrade, "Articles on Various Subjects Dealing with the History of the City of Richmond" (Richmond: Dept. of Public Works, 1949), p. 130.

¹² Joseph C. Robert, The Tobacco Kingdom: Plantation, Market and Factory in Virginia and North Carolina, 1800-1860 (Durham: Duke University Press, 1938), p. 77.

¹³ Ibid., p. 189. Antebellum manufactured tobacco was chewing, not smoking, tobacco.

¹⁴ Richmond Whig and Public Advisor, December 1, 1837.

¹⁵ Robert, p. 189.


¹⁶ James Cox, "Six Buildings Worth Keeping," Arts in Virginia 15 (Fall 1974): 23. It should be noted here that in the 1860s the concentration changed from the manufacture of chewing to plug and twist tobacco.

¹⁷Robert Brock, Richmond as a Manufacturing and Trading Center (Richmond: Jones & Cook, 1880), p. 6.

¹⁸Ibid.

¹⁹Mary Wingfield Scott, Old Richmond Neighborhoods (Richmond: Whittet and Shepperson, 1950), pp. 64-67.

National Register of Historic Places Inventory—Nomination Form



Page 9,1

8. SIGNIFICANCE


- ²⁰LaPrade, p. 14.
- ²¹Sanford, p. 143.
- ²²Dabney, p. 163.
- ²³Sanford, (Book 2, Part 1), p. 10.
- 24B. W. Arnold, Jr., "History of the Tobacco Industry in Virginia from 1860 to 1894," Johns Hopkins University Studies in History and Political Science 15 (I-II) (January February 1897): 19-23.
- 25R. A. Brock, <u>Richmond as a Manufacturing and Trading Center</u> (Richmond: Jones and Cook, 1880).
- 26Joseph C. Robert, The Story of Tobacco in America (N.Y.: Alfred A. Knopf, 1949), pp. 145-146.
 - 27"75 Years, Larus & Brothers Company, 1877-1952." (Pamphlet.)
- ²⁸The Belle Bossieux is currently undergoing restoration by the Historic Richmond Foundation.
 - ²⁹Samuel Mordecai, <u>Richmond in By-Gone Days</u> (Richmond: West & Johnston, 1860), p. 47.
- 30Myron Berman, Richmond's Jewry, 1769-1976: Shabbat in Shockoe (Charlottesville:
- University Press of Virginia, 1979), pp. 344-45.
 - 31Mary Wingfield Scott, p. 67.

9. MAJOR BIBLIOGRAPHICAL REFERENCES

- Brock, Robert. Richmond as a Manufacturing and Trading Center. Richmond: Jones and Cook, 1880.
- Cox, James. "Six Buildings Worth Keeping." Arts in Virginia. 15, (Fall, 1974): 22-31.
- Dabney, Virginius. Richmond: The Story of a City. New York: Doubleday and Co., Inc., 1976.
- Heimann, R. K. Tobacco and Americans. New York: McGraw-Hill Book Co., Inc., 1960.
- Hening, William, ed. The Statutes at Large. Richmond: Printed for the Editor by George Cochran, 1822.
- LaPrade, David. "Articles on various subjects dealing with the history of the City of Richmond." Department of Public Works, City of Richmond, 1949. (Typewritten).
- Mordecai, Samuel. Richmond in By-Gone Days. Richmond: West & Johnston, 1860; reprint ed., Richmond: The Dietz Press, Inc., 1946.
- Richmond, City of. Council Minutes, Vol. 7, August 16, 1819, p. 22.
- Richmond Whig and Public Advisor, December 1, 1837.
- Robert, Joseph C. The Story of Tobacco in America. New York: Alfred A. Knopf, 1949.
- . The Tobacco Kingdom: Plantation, Market and Factory in Virginia and North Carolina, 1800-1860. Durham: Duke University Press, 1938.
- Sanford, James, ed. Richmond, Her Triumphs, Tragedies and Growth. Richmond: Richmond Chamber of Commerce. 1975.
- Scott, Mary Wingfield. Houses of Old Richmond. Richmond: Valentine Museum, 1941.
- . Old Richmond Neighborhoods. Richmond: Whittet and Shepperson, 1950; reprint ed., Richmond: William Byrd Press, Inc., 1975.
- "75 Years, Larus and Brothers Company, 1877-1952." (Pamphlet.)
- Stanard, Mary Newton. Richmond: Its People and Its Story. Philadelphia: J.B. Lippincott Co., 1923.
- Waitt, Robert. Confederate Military Hospitals in Richmond. Richmond: Richmond Civil War Centennial Committee, 1964.
- Wright, Louis, ed. The Prose Works of William Byrd of Westover. Cambridge: Belknap Press of Harvard University Press, 1966.

National Register of Historic Places Inventory—Nomination Form

Shockoe Valley and Tobacco Row Historic District, Richmond, VA Continuation sheet Item number 2,6,10



Page

LOCATION

Bounded on the west by the Seaboard Coast Line RR from Dock St. to Creek Alley, by the E. side of 15th St. from Creek Alley to E. Broad St., and by the W. side of 16th St. from E. Broad to E. Clay sts.:

Bounded roughly on the north by the 1600 and 1700 blocks (s. side) of E. Clay St., the 1800 (s. side) and 1900 (partial n. side) blocks of E. Broad St., the 1900 (partial s. side) and 2000 (s. side) blocks of E. Grace St., the 2100 block (s. side) of E. Franklin St., and by the south line of the St. John's Church Historic District: the 2200-2700 blocks (n. side) of the alley between E. Franklin and E. Main sts. and the 2800 block (n. side) of E. Main St.;

Bounded on the east by the W. side of Peach St.; and bounded on the south by the north line of the James River and Kanawha Canal Historic District: the n. side of Dock St. from Peach St. to the Seaboard Coast Line RR. See Item 10: Verbal Boundary Description for more detailed description of boundary.

REPRESENTATION IN EXISTING SURVEYS

(2) Virginia Historic Landmarks Commission Survey 1967, 1980 Virginia Historic Landmarks Commission 221 Governor Street Richmond, Virginia 23219


GEOGRAPHICAL DATA

Verbal boundary description

Beginning at a point on N side of Dock St. at the intersection with the westernmost Seaboard Coast Line track, about 540' SE of the intersection of Dock and S. 14th sts.; thence about 630' NE along said track, following E side of Spruce Alley for last 150', to N side of Creek Alley; thence about 160' NW along said side of alley to E side of S. 15th St.; thence about 550' NE along said side of street, passing under I-95, to N side of E. Franklin St.; thence about 50' NW along said side to 32' contour (between retaining wall and 1500 E. Franklin); thence following said contour about 750' NE to S side of E. Broad St.; thence about 170' SE along said side to W side of N. 16th St.; thence about 800' NE along said side, crossing E. Marshall St. and continuing to a point in line with S side of E. Clay St.;

Thence continuing about 800' SE along said side of E. Clay to W side of N. 18th St.; thence about 50' SW along said side; thence about 300' SE, crossing N. 18th, to W side of N. 19th St.; thence about 120' S, then about 100' SSW along said side; thence about 350' NW, following RR track for last 250', to W side of N. 18th; thence about 630' SW along said side, crossing E. Marshall, to S side of E. Broad; thence about 380' SE along said side to E side of N. 19th St.; thence about 240' NE along said side to N property line of 311 N. 19th; thence about 220' SE to a point in line with the E property line of 1916 E. Broad; thence about 240' SW to S side of E. Broad; thence about 60' SE along said side to W side of N. 20th St.; thence about 60' SW along said side; thence about 130' NW to W side of alley between N. 19th and N. 20th; thence about 340' SW along said side of alley to S side of E. Grace St.; thence about

National Register of Historic Places Inventory—Nomination Form



Page 2

LO. GEOGRAPHICAL DATA

<u>Verbal</u> boundary description (Cont.)

470' SE along said side to W side of N. 21st St.; thence about 400' SW along said side to S side of E. Franklin; thence about 400' SE along said side to E side of N. 22nd St.; thence about 170' SW along said side to N side of alley between E. Franklin and E. Main sts.; thence about 1,780' SE along said side of alley, crossing N. 23rd, N. 24th, N. 25th, N. 26th, and N. 27th, and continuing beyond latter street to a point about 110' NE of 2708 E. Main;

Thence extending about 140' SW to N side of E. Main; thence about 480' SE along NE side of E. Main; thence about 460' SW, crossing said street and continuing SW along W side of Peach St., to N side of Dock St.;

Thence extending about 380' NW, then about 1,520' NW, then about 100' W, then about 1,400' NW --all along N side of Dock St. to E side of S. 18th; thence about 70' W, then about 250' NW along said side of Dock to E side of S. 17th; thence about 230' SW along said side, beneath I-95, to N side of Dock, then continuing about 430' along said side to point of origin.

(See Continuation Sheet #15)

7. DESCRIPTION--Inventory (continued)

The following structures were determined to be non-contributing elements because they did not conform to the rest of the district in style, scale, or materials:

Rear of 1604 E. Broad St.

1615 E. Broad St.

1719-21 E. Broad St.

1813 E. Broad St.

1704 E. Franklin St.

1715 E. Grace St.

2314 E. Main St.

2506 E. Main St.

121-123 N. 17th St.

200 N. 18th St. (NW corner of N. 18th and E. Grace St.)

201 N. 18th St.

National Register of Historic Places Inventory—Nomination Form

Shockoe Valley and Tobacco Row Historic District, Richmond, VA

Continuation sheet | 14 / Item number 7



Page

DESCRIPTION

This report is the result of a ten-week internship held at the Virginia Historic Landmarks Commission during the summer of 1980. Most research and survey was done by University of Virginia students Karen Lang-Kummer and A. Rebecca Harrison, working under the direction of Barry N. Zarakov. Also aiding in the research and final preparation of this report were Robert A. Carter and Margaret T. Peters, staff-historians of the Virginia Historic Landmarks Commission.

National Register of Historic Places Inventory—Nomination Form

Shockoe Valley and Tobacco Row Historic District, Richmond, Virginia

Continuation sheet

#15

Item number

7

Page

For HCRS use only

received

date entered

7. DESCRIPTION -- Inventory (arranged alphabetically by the name of the street)

* NONCONTRIBUTING STRUCTURES

AMBLER STREET

100 Block

109 (Swift and Company): brick (5-course American bond); 3 stories; flat roof; 5 bays. Produce warehouse. Commercial vernacular. 1910. Architect: C. H. Kane; builder: A. C. Bedford.

West side between East Franklin and East Grace (C & O Railroad Viaduct): Heavy member steel viaduct supporting elevated train tracks. Area to east of viaduct is gravel and weed parking lot with one unused railroad track that runs parallel down north half of lot and has old flatcar parked on it.

West side under railroad viaduct: brick (5-course American bond); 1 story; shed roof; 2 bays. Railroad. Builder's vernacular. Mid-20th century.

EAST BROAD STREET

1500 Block

1500 block, south side, between expressway and elevated railroad viaduct: brick (6-course American bond); l story; gable roof (slate); l bay. Utility. Industrial vernacular. 1927. Builder: City of Richmond.

1500 block, south side, under west elevated Seaboard railroad viaduct: brick (5-course American bond); I story; flat roof; I bay. Railroad. Builder's vernacular. Ca. 1935.

1600 Block

1604: brick (5-course American bond); 1 story; flat roof; 3 bays. Commercial (whole-sale office). Commercial vernacular. Ca. 1946.

To rear of 1604 (Coal bins): Heavy wood member construction. Elevated on wood piers with concrete bases. Bins are slightly funnel shaped with flat bottom. Shoots exit from bottom of bins on either side (west/east.) Coal heap to east and spall-block drive to west. Steps to top of bin at south.

Rear of 1604: corrugated metal and steel; 1 story; shed roof (metal); 8 bays. Garage. Builder's vernacular. Ca. 1975.*

1600 block, to west, rear, of 300 N. 17th: wood frame (board and batten); 1 story; gable roof; 2 bays; 1-story, 2-bay porch. Railroad. Pailroad vernacular. Ca. 1930. Building and porch elevated on concrete piers. Wood plank porch floor with simple railing, straight flight wood stairs, 6/6-light sash with wood sill, metal hood over top sash. Building roof continues to form porch roof with diagonal bracing at corners, rake boards, board and batten typanum.

National Register of Historic Places Inventory—Nomination Form

Shockoe Valley and Tobacco Row Historic District, Richmond, Virginia

Continuation sheet #16 Item number

For HCRS use only
received
date entered

Page

DESCRIPTION -- Inventory (continued)

EAST BROAD STREET (continued)

1600 Block (continued)

1600 block, south side, between Crane and N. 17th: vacant lot. Concrete-paved vacant lot used for parking. Single tree in middle of south side.

1615: brick (stretcher bond); 1 story; flat roof; 7 bays. Gas station. International style (remodelling.) 1957.*

1700 Block

1700 block, south side, southeast corner of East Broad and N. 17th: vacant lot. Weed-covered vacant lot. Large billboard in northwest corner of lot. Small trees along south side.

1712: brick (6-course American bond); 1 story; flat roof; 8 bays. Industrial. Industrial vernacular. Ca. 1945.

1719-21: stucco over brick; 1 story; flat roof; 8 bays. Service garage. Ca. 1940. Recessed single door in 2nd bay from east. Small single doors to restrooms in 4th and 5th bays from east. 3 large overhead garage doors in west 3 end bays.*

1724: stucco over brick; 1 story; gable roof (pan tiles); 3 bays. Commercial (office.) Builder's vernacular. Ca. 1945. Center bay, single pedestrian entrance flanked by single-light, plate-glass windows with brick header row sills. All 3 opening bays slightly recessed. Building on concrete base. Pent roof. False chimneys at east and west sides.


1800 Block

1801 (The (Old) Branch Public Baths): brick (Flemish bond); 2 stories; shed roof; 4 bays. Commercial (office and store.) Commercial vernacular. 1908. Architect: Archer and Allen (Baltimore, Maryland); builder: W. A. Christuman. East and west bay entrances: double wood ped.doors with wood panel in transom, stone sills, 1; soldier-course brick surrounds. Center bay entrance: single pedestrian door, transom filled in stone sill.

1805-07-09: brick (stretcher bond); 2 stories; shed roof; 9 bays. Commercial (store with residences above.) Commercial vernacular. 1911. Builder: Davis & Archer. Single-door entrances with transoms and stone sills in 1st, 3rd, 4th, 6th, 7th, and 9th bays from east with 6th and 9th bays recessed. Cast-iron and wood storefronts with two plate-glass windows with wood panels below in 2nd, 5th, and 8th bays; transom across storefronts; molded cornice with plain frieze and brackets at each major division 2nd floor divided into 3 major divisions by brick piers with window bays recessed between. 1/1-light sash with rough-faced stone sills and lintels. Decorative corbelled brickwork above; applied-metal cornice with plain frieze; brick parapet with piers projecting above roof line.

National Register of Historic Places Inventory—Nomination Form

Shockoe Valley and Tobacco Row Historic District, Richmond, VA Continuation sheet #17 Item number 7



Page

. DESCRIPTION -- Inventory (continued)

EAST BROAD STREET (continued)

1800 Block (continued)

1813: glass and metal over concrete block; 1 story; flat roof; 4 bays (originally). Gas station. Commercial vernacular. Ca. 1952. Single-door entrance with boarded-up transom in 2nd bay from east.*

1900 Block

1901: brick (stretcher bond); 2 stories; shed roof with false mansard (slate), pyramidal over west bays; 4 bays. Double house (only west half.) Queen Anne. Ca. 1890. Entrance in east bay; single wood pedestrian door, single light, horizontal transom, rough-faced stone lintel, stone sill, above concrete block and wood platform/stoop. Queen Anne hood with decorative frieze and diagonal braces. West 3 bays project to form bay window. Windows are 1/1-light sash, rough-faced stone sills and lintels. Plain box gutter cornice with end brack

1904: brick (6-course American bond); 1 story; parapet roof; 1 bay. Garage. Builder's vernacular. Ca. 1930.

1908-10: brick (9-course American bond with Flemish bond); 2 stories on raised basement; shed roof; 6 bays. 1908: 1-story, Greek Revival porch in east bay. 1910: 1-story, 3-bay, late 19th-century porch addition across facade. 2 of a triple house. Italianate. Ca. 1875. Decorative applied Italianate cornices with scroll-sawn, paired brackets having plain panels between pairs. Metal coping.

1912-14-16: brick (stretcher bond); 2 stories; shed roof; 9 bays; 1-story, 9-bay wood porch, scroll-sawn with turned posts with brackets and decorative balustrade. Row house (3). Italianate vernacular. Ca. 1875.

1917: concrete block; 1 story; flat roof; 3 bays. Ice cream stand. Commercial vernacular/Moderne. Ca. 1950. Entrance is single door with concrete sill in west end bay. Wide overhang metal roof with center section over projecting bay curving outward.

EAST CARY STREET

1500 Block

1510: stucco over brick; 1 story; gable roof (standing-seam metal); 4 bays. Industrial. Industrial vernacular. Ca. 1911. Builder: Davis and Archer. Wood, interior-sliding delivery door with steel lintel in west end bay; single wood door with metal lintel in east end bay.

1512: brick (6-course American bond); l story; flat roof; 2 bays. Commercial (office and stone). Commercial vernacular. Ca. 1910. Double, sliding, wood delivery entrance; doors slide on applied-wood frame in front of building.

Across from 1512, south side: vacant lot. Weed and gravel lot. Concrete piers supporting railroad overpass runs north-south across lot.

1500 block, south side, under expressway: lot. Mid-20th century.

1500 block, north side, under expressway: parking lot. Wedge-shaped, gravel lot used for parking.

 $(x^{(i)}, \lambda_{i+1}, \lambda_{i+1}, \dots, \lambda_{i+1}, \lambda_{i+1}, \lambda_{i+1}, \lambda_{i+1}, \dots, \lambda_{i+1}, \lambda_{$

(See Continuation Sheet #18)

National Register of Historic Places Inventory—Nomination Form

Shockoe Valley and Tobacco Row Historic District, Richmond, Virginia

Continuation sheet

#18

Item number

7

Page

received

date entered.

For HCRS use only

DESCRIPTION -- Inventory (continued)

EAST CARY STREET (continued)

1500 Block (continued)

1545-49: brick (6- and 7-course American bond with cement stucco over 1st-story brick) 2 stories; shed roof; 8 bays. Industrial. Commercial vernacular. Ca.1920. Ent.: singl metal pedestrian door under segmental arch, stone sill. Projecting brick pier divides elevation in half with 4 bays to each side.

1700 Block

1712-14: brick (6-course American bond); 5 stories; 3 bays. Industrial warehouse. Commercial vernacular. Ca. 1920. Double wood delivery doors off elevated platform. 3 structural bays recessed between projecting brick piers having concrete bases and capitals. Triple, 4/4-light sash windows in each window bay.

1717-21: brick (6-course American bond); 5 stories; flat roof; 9 bays. Industrial. Industrial vernacular. Ca. 1914. Architect: Scarborough. Recessed, metal, interiorsliding delivery doors with stone sills and triple-header brick segmental arches in 4th and 6th bays from east. Detailing identical with building at 20-28 S. 18th (north across Cary Street.)

1800 Block

1805: west half of building: brick (stretcher bond), east half of building: concrete block; l story; flat roof; 3 bays, including concrete block addition as 1 bay. Commercial. Builder's vernacular. Core: ca. 1930; brick addition: ca. 1950; concrete block addition: ca. 1960. Single wood door pedestrian entrance in center bay with brick header-course jack arch and concrete sill.

1900 Block

1900, northeast corner of E. Cary and S. 19th, (U. S. Tobacco Building/Cardwell Machine Company); brick (heavily painted); 4 stories; gable roof; 6 bays. Industrial. Industrial vernacular. 1893. Tall, recessed entrance bay in center with 3 stone steps and quadruple-header brick segmental arch. Multi-light sash windows, some altered, with triple-header brick segmental arches.

2000 Block


2010 (Climax Warehouse): brick (5-course American bond); 3 stories; shed roof; 21 bays. Industrial warehouse. Industrial vernacular. 1899. Concrete loading docks between 2nd and 10th bays from east and west ends. Double metal shutters on windows with stone sills, 1st and 2nd floors with double-header brick segmental arches, 3rd floor with flat-topped brick soldier-course segmental arches. Cornice similar to Kinney Building, 2500 E. Cary. Building identical to Carolina Warehouse, 2200 E. Cary.

National Register of Historic Places Inventory—Nomination Form

Shockoe Valley and Tobacco Row Historic District, Richmond, VA

Continuation sheet #19

Item number



Page

DESCRIPTION -- Inventory (continued)

EAST CARY STREET (continued)

2200 Block

2200 (Carolina Warehouse): brick (5-course American bond); 3 stories; flat roof; 7 bays. Industrial warehouse. Industrial vernacular.

2201: brick (6- and 7-course American bond); 2 stories; flat roof; 6 bays. Commercial (office) and Industrial. Commercial/Industrial vernacular. Ca. 1925, ca. 1970store front.

2202: brick (6-course American bond); 3 bays; parapet roof; 5 bays. warehouse. Industrial vernacular. Ca. 1940.

2400 Block

2400 (Cameron Annex of American Tobacco Company): brick (5-course American bond with Flemish bond every 5th row and every 7th row on east 7 bays; 4 stories; flat roof; 31 bays, 26 on 1st floor. Industrial warehouse. Industrial vernacular.

2500 Block -- See appendix (Continuation Sheet #51)
Block

2600-16 (S. 26th Street facade): brick (6-course American bond); 6 stories; flat roof 6 bays. Industrial. Industrial Art Deco. 1929-30.

2620-30: brick (6-course American bond); lower floor area with large open space above about 3 floors; parapet roof; 3 bays. Industrial power plant. Art Deco. 1930.

EAST CLAY STREET

1700 Block

1709: brick (5-course American bond); 5 stories; parapet and flat roof; 4 structural bays in 3 major sections. Industrial. Industrial vernacular. Ca. 1911.


1711: brick (6-course American bond); 3 stories (exterior); parapet roof; 5 bays. Industrial warehouse. Industrial vernacular. 1911.

1713, southwest corner of N. 18th and E. Clay streets, also has 420 N. 18th address and entrance: brick (6-course American bond); 2 stories; flat roof; 6 bays. trial (office 2nd floor). Industrial vernacular. Ca. 1920.

(See Continuation Sheet #20)

National Register of Historic Places Inventory—Nomination Form

Shockoe Valley and Tobacco Row Historic District, Richmond, VA Continuation sheet #20 | Item number 7



Page

7. DESCRIPTION -- Inventory (continued)

CRANE STREET

200 Block

West side, between E. Grace and E. Broad streets: railroad lot.

201, southeast corner between Crane and E. Grace streets: concrete block; 1 story; shed roof; 1 bay. Commercial (store). Builder's remodeling. Ca. 1970 on ca. 1900 building.

203: brick (6-course American bond); 2 stories; shed roof; 4 bays. Garage, storage above. Commercial vernacular. Ca. 1920.

√ 205: brick (6-course American bond); 1 story; shed roof (standing-seam metal); 2 bays
 Garage. Builder's commercial. Ca. 1950.

DOCK STREET

1600 Block

North side, between S. 16th and S. 17th streets: lots.

1700 Block

1701: brick (6-course American bond); 2 stories; shed roof that slopes down toward facade; 5 bays. Industrial. Industrial vernacular. Ca. 1890.

2200 Block

2204: concrete and metal; 1½ stories; flat roof (composition); 5 bays, 4 on 1st floor; 1-story porch that runs entire length of building over elevated platform, flat roof supported on cylindrical metal columns, metal gutter, composition roof. Industrial. Industrial/Builder's vernacular. Ca. 1945.

bays. Industrial. Builder's Industrial vernacular. Ca. 1950.

EAST FRANKLIN STREET

1500 Block

1500: brick (stretcher bond); 2 stories; parapet and flat roof; 3 bays. Commercial (store). 1909.


North of E. Franklin, rear of 1500 E. Franklin (Freight depot for Seaboard Co.): brick (stretcher and 5-course American bond); 1 story; flat roof; 22 structural bays. R.R. freight warehouse. Commercial. Ca. 1910. Builder: J.T. Yuckols.

National Register of Historic Places Inventory—Nomination Form

Shockoe Valley and Tobacco Row Historic District, Richmond, VA

Continuation sheet #21

Item number 7



Page

DESCRIPTION -- Inventory (continued)

EAST FRANKLIN STREET (continued)

1500 Block (continued)

1520: wood frame (weatherboard siding); 1 raised story; shed roof; 2 bays. Railroad. Industrial vernacular. 1910.

1600 Block

1600: brick (6-course American bond); 2 stories; flat roof; 1 bay-1st floor, 3 bays-2nd floor; 1-story, 3-bay porch, concrete and brick elevated platform and metal shed roof also extends across building to east, thin, cylindrical metal support columns. Commercial (office and store). Commercial vernacular. Ca. 1915.

1606: brick (stretcher bond); 3 stories; shed roof; 3 bays-1st floor, 4 bays-2nd and 3rd floors. Commercial (office and store). Commercial vernacular. Ca. 1890.

1605-07: parking lot.

1609: brick (5-course American bond); 1 story; shed roof; 7 bays. Produce warehouse. Commercial vernacular. Ca. 1935.

1617: brick (stretcher bond); 3 stories; flat roof; 3 bays. Commercial (office and store). Greek Revival. Ca. 1852, enlarged in 1856 by George Carrington.

1700 Block

1703: brick (stretcher bond); 2 stories; flat roof; 3 bays. Commercial (office). Commercial Italianate. Ca. 1875, ca. 1972 remodelled storefront.

1704: concrete block; I story; shed roof; 2 bays. Commercial (store). Builder's vernacular. Ca. 1960.*

1705: brick (stretcher bond); l story; flat roof; 3 bays. Commercial (store). Commercial vernacular. Ca. 1930, 1973 remodelled storefront.

1707: brick (stretcher bond - storefront, 2nd floor-can't distinguish under paint); 2 stories; shed roof that slopes north; 3 bays. Commercial (store). Commercial vernacular. Ca. 1890, new front-1972.

1708: See appendix (Continuation Sheet #51)

1709: brick (10-course American bond); 2 stories; flat roof; 3 bays. Commercial (store). Commercial vernacular. Ca. 1910, new front-1972.


1710 (Anson Richards House): brick (stretcher bond); 3½ stories; gable roof (standing-seam metal); 2, gable dormers; 3 bays. Commercial (store), residence above. Greek Revival. Ca. 1842. Architect/builder: Anson Richards.

(See Continuation Sheet #22)

National Register of Historic Places Inventory—Nomination Form

Shockoe Valley and Tobacco Row Historic District, Richmond, VA

Continuation sheet #22 Item number 7



Page

7. DESCRIPTION -- Inventory (continued)

EAST FRANKLIN STREET (continued)

1700 Block (continued)

1711-1713: brick (stretcher bond); 2 stories; shed roof; 6 bays, 2 major divisions. Commercial (office and store). Commercial vernacular. Ca. 1913, new front 1959 and 1961. Architect: Aubrey L. Hunt, builder: S. J. Hunt.

1712: brick (6-course American bond); 1 story; shed roof; 3 bays. Commercial (office Builder's vernacular. Ca. 1950 facade on 1880s building.

1714-16: brick (7-course American bond); 2 stories; shed roof; 7 bays. Commercial (office and store). Late Commercial Italianate. Ca. 1909. Builder: T. D. Newell.

1717: brick (stretcher bond); 3 stories; shed roof; 9 bays-1st floor, 6 bays-2nd and 3rd floors. Commercial (office and store) and residential. 2nd Renaissance Revival vernacular. Ca. 1910, ca. 1970 storefront. Architect: Charles H. Fisher, builder: James Fox & Sons.

1718: brick (5-course American bond); 1 story, shed roof; 3 bays. Commercial restaurant. Builder's Commercial vernacular. Ca. 1950.

1719-21: brick (stretcher bond); 2½ stories; gable roof (standing-seam metal); 4 bays. Commercial (store) with residence above. Modified Greek Revival and Commercial vernacular. 1817, 1909. Builder: Charles Whitlock.

1800 Block

1801: brick (stretcher bond and 2 rows of 6-course American bond); 1 story; flat roof; 4 bays. Commercial (store-wholesale). Commercial vernacular. Ca. 1948.

1802-04: brick (stretcher bond); 2 stories; parapet roof; 5 bays. Commercial (store) with residence above. Commercial Italianate. Ca. 1880, remodelled storefront.

1805-07: wood frame (weatherboard siding); 2 stories with basement; hipped roof (standing-seam metal); 3 bays; 1-story (elevated), 1-bay (center) porch, wood, classica pedimented portico with Tuscan piers and 2 Doric columns, dentiled cornice similar to main cornice, full entablature, broad flight of wood stairs. Lodge. Federal. 1785-87. Builder: Richmond Lodge #13.


1810: brick (5-course American bond); 3 stories; parapet roof; 5 bays-1st and 3rd floors, 1 bay-2nd floor. Commercial (office and store). Commercial vernacular. Early 20th century.

1809-1811: brick (9-course American bond); 2 stories; gable roof (composition); 3 bays. Commercial (store-wholesale), formerly stable. Commercial vernacular. Ca. 1890.

National Register of Historic Places Inventory—Nomination Form

Shockoe Valley and Tobacco Row Historic District, Richmond, VA

Continuation sheet #23 Item number 7



Page

7. DESCRIPTION -- Inventory (continued)

EAST FRANKLIN STREET (continued)

1800 Block (continued)

1813: brick (9-course American bond); 2 stories; false mansard roof (slate on Mansard); 2 bays-1st floor, 3 bays-2nd floor. Commercial (store-wholesale). Builder's Commercial vernacular. 1890.

1814-16: brick; 2 stories; flat roof; 9 bays. Commercial. Commercial vernacular. Ca. 1910, ca. 1970 remodelled storefront. Builder: C. E. Haywood.

1815: brick (9-course American bond); 2 stories; false mansard roof (slate on mansard); 3 bays. Commercial (store-wholesale). Builder's Commercial vernacular. Ca. 1890.

1817: brick (stretcher bond); 2 stories; flat roof; 2 bays-1st floor, 3 bays-2nd floor. Commercial (store-wholesale). Builder's vernacular. Ca. 1957. Builder: J. L. Vogel.

1900 Block

1900: brick (5-course American bond); 4 stories; gable roof (standing-seam metal); 11 bays. Industrial. Industrial vernacular. 1853, wing-1877. Builder: William Grant, architect: Samuel Freeman.

1910: concrete block; 1 story; shed roof; 3 bays. Commercial (store). Builder's vernacular. Ca. 1950.

East of 1910, northwest corner of E. Franklin and N. 20th: vacant lot.

1921: vacant lot.

1923: brick (6-course American bond); 2 stories; flat roof; 3 bays-1st floor, 5 bays-2nd floor. Garage (working). Commercial vernacular. Ca. 1910. Architect: S. M. Williams.

2000 Block

2000: stucco; l story; flat roof; l bay. Commercial (under renovation-bar). Commercial vernacular. Ca. 1940.


2001: brick (stretcher bond); 2 stories; flat roof; 12 bays. Industrial. Industrial vernacular. Ca. 1890.

2001: brick (stretcher bond); 2 stories; parapet roof; 2 bays. Commercial (office). Industrial vernacular. Ca. 1900.

National Register of Historic Places Inventory—Nomination Form

Shockoe Valley and Tobacco Row Historic District, Richmond, VA

Continuation sheet #24 | Item number 7



Page

7. DESCRIPTION -- Inventory (continued)

EAST FRANKLIN STREET (continued)

2000 Block (continued)

2003: brick (6-course American bond); 2 stories; flat roof; 4 bays-1st floor, 3 bays-2nd floor. Industrial with offices above. Industrial vernacular. Ca. 1955.

2004-06 (P. Whitlock's Cheroot & Cigar Factory): brick (7-course American bond); 5 stories; gable roof; 6 bays, 2 structural bays. Industrial. Industrial vernacular. Ca. 1888.

2005-07: brick (6-course American bond), concrete block - side bearing walls; 2 stories; flat roof; 9 bays. Commercial (office). Commercial vernacular. 1960. Architect: Morris.

2009 (Old Hebrew Cemetery): 1791; Isaiah Isaacs.

2016, extension of 2018, which is addition to 2020: brick (6-course American bond); 1 story; parapet and flat roof; 3 bays. Commercial. Commercial vernacular. Ca. 1947.

2018, addition to 2020: concrete block; 2 stories; flat roof; 1 bay-1st floor, 2 bays-2nd floor. Industrial. Industrial vernacular. Ca. 1967.
2020: See appendix (Continuation Sheet #51)

2100 Block

Southwest corner E. Franklin and N. 21st streets: vacant lot.

2101-1: brick (stretcher bond); 2 stories; shed roof; 6 bays. Double house. Builder's vernacular. Ca. 1880.

 \sim 2103-05: parking lot.

EAST GRACE STREET

1600 Block

1601-05, Ambler facade, southeast corner Ambler and E. Grace streets: brick (7-course American bond); 3 stories; flat roof; 5 bays-1st floor, 8 bays-2nd and 3rd floors. Industrial produce warehouse. Commercial Italianate. Ca. 1870.

1700 Block


1715: concrete block; 1 story; flat roof; 1 bay. Commercial (store). Builder's vernacular. Ca. 1960.*

1800 Block

1805: brick (stretcher bond); 2 stories; gable roof (standing-seam metal); 3 bays.

National Register of Historic Places Inventory—Nomination Form

Shockoe Valley and Tobacco Row Historic District, Richmond, VA Continuation sheet #25 | Item number 7



Page

DESCRIPTION -- Inventory (continued)

EAST GRACE STREET (continued)

1800 Block (continued)

1809½-1811: wood frame (weatherboard siding); 2½ stories; gable roof (standing-seam metal on east half, composition on west half); 2, gable dormers; 6 bays; 1-story, 1-bay (side) porch on west half, 2-story, 1-bay (side) porch on east half. Double house. Greek Revival. Ca. 1845. Builder: Andrew Lockwood and W. Holt Richardson.

1812 (Adam Craig House): wood frame (beaded weatherboard siding); 2 stories; gable roof (standing-seam metal); 5 bays; 1-story, 1-bay (center) porch. Detached town house. Federal. 1784-87, restored 1936 by A.P.V.A.

1812, rear of Adam Craig House: brick (5-course American bond); 2 stories; gable roof (slate); 4 bays. Outbuilding. Vernacular. Ca. 1815.
1813-15: See Appendix -- Continuation Sheet #52

1900 Block

1907: brick (5- and 7-course American bond); l story; shed roof; 2 bays. Garage. Builder's vernacular. Ca. 1911.

Southwest corner E. Grace and N. 20th streets: vacant lot.

2000 Block

2009, 21st and E. Grace streets, southwest corner: brick (stretcher bond) and reinforced concrete; 5 stories; flat foor; 8 bays, 7 structural bays. Industrial. Industrial vernacular. Ca. 1912. Architect: J. P. Worcester and Company.

MAIN STREET

1500 Block

 $^{\sqrt{1}}$ 1500, north side, west of Main Street Station: parking lot.

 $\sqrt{1501}$, southeast corner of S. 15th and E. Main streets: parking lot.

1505: brick (stretcher bond); 2 stories; shed roof; 2 bays. Commercial. Commercial vernacular. Ca. 1920.


1507: brick (stretcher bond); 2 stories; shed roof; 1 bay. Commercial (office). Commercial vernacular. Ca. 1920.

Between 1507 and 1547, south side E. Main Street, across from Main Street Station: parking lot.

National Register of Historic Places Inventory—Nomination Form

Shockoe Valley and Tobacco Row Historic District, Richmond, VA

Continuation sheet #26 | Item number 7



Page

7. DESCRIPTION -- Inventory (continued)

MAIN STREET (continued)

1500 Block (continued)

1520 (Main Street Station): brick (stretcher bond) and Roman tile with terra cotta and stone decoration; 2½ and 3 stories; hipped roof (tile); 11, pedimented, hipped dormers; 7 bays; 1-story, 5-bay porch. Railroad station. Second Renaissance Revival. 1900-1901. Architect/builder: Wilson, Harris and Richards (Philadelphia).

Rear 1520, Main Street Station train shed: steel truss system. Railroad. Railroad vernacular. Ca. 1900. Builder: Pencoyd Iron Works of Pencoyd, Pennsylvania. Engineer: F. W. Scarborough of C & O Railroad.

Rear of 1534: corrugated metal; I story; gable roof (standing-seam metal); I bay. Railroad. Industrial vernacular. Mid-20th century.

1547: brick (8-course American bond); 3 stories; shed roof; 4 bays-1st floor, 3 bays-2nd and 3rd floors. Commercial (store). Commercial vernacular. Ca. 1915.

1549: brick (8-course American bond); 2 stories; shed roof; 3 bays-1st floor, 2 bays-2nd floor. Commercial (store). Commercial vernacular. Ca. 1923.

 $\sqrt{2}$ 1551: vacant lot.

1552 (Railroad YMCA): brick (stretcher bond); 2½ stories; hipped roof (composition); 3 bays; 1-story, 3-bay porch. (Old) railroad YMCA. Beaux Arts classical. 1907 - from shield insignia above 1st floor window openings.

1553-55: brick (stretcher bond); 3 stories; shed roof; 6 bays, 2 major divisions. Commercial. Commercial vernacular. Ca. 1910.

1557: See Appendix -- Continuation Sheet #52

1559: brick (stretcher bond); 2 stories; parapet roof; 4 bays-lst floor, 3 bays-2nd floor. Commercial (store) with residence on 2nd floor. Commercial vernacular. Ca. 1913. Architect/builder: George Ware.

1561: brick (stretcher bond); 2 stories; shed roof; 3 bays. Commercial (store). Commercial vernacular. Ca. 1910.


1700 Block

1700-02: brick (stretcher bond); 2 stories; parapet roof; 5 bays-1st floor, 4 bays-2nd floor. Commercial (store). Commercial vernacular. Ca. 1912, facade altered 1955 Architect: A. F. Huntt, builder: James Fox and Sons.

(See Continuation Sheet #27)

National Register of Historic Places Inventory—Nomination Form

Shockoe Valley and Tobacco Row Historic District, Richmond, VA Continuation sheet #27 | Item number 7



Page

DESCRIPTION -- Inventory (continued)

MAIN STREET (continued)

1700 Block (continued)

1701: brick (stretcher bond); 3 stories; shed and fake pediment roof; 5 bays-1st floor 3 bays-2nd and 3rd floors. Commercial (store). Commercial vernacular, builder's remodelling. Ca. 1905.

1704-06: brick (stretcher bond); 3 stories; shed roof; 7 bays-1st floor, 4 bays-2nd floor. Commercial (store). Commercial Italianate. Ca. 1885.

1705: See appendix (Continuation Sheet #51)

1707: brick (stretcher bond); 2 stories; parapet roof; 3 bays. Commercial. Commercial vernacular. Ca. 1917, ca. 1972 remodelled storefront after flood. Builder: E. H. Armestead.

1708-1710: brick; 2 stories; parapet roof; 4 bays. Commercial (store). Commercial vernacular. Ca. 1890.

1711: brick (stretcher bond); 3 stories; shed roof; 4 bays. Commercial (store). Art Deco influence on Commercial vernacular. Ca. 1925.

1712: brick (stretcher bond); 2 stories; parapet roof; 2 bays. Commercial (store). Commercial vernacular. Ca. 1915, remodelled 1963. Architect: D. Wiley Anderson.

1713: glass and metal (probably on brick bearing wall); 1 story; parapet roof; 5 bays. Commercial (store). Builder's remodelling. Ca. 1930 remodelling of early 20th century building.

1714: brick (stretcher bond); 2 stories; parapet roof; 3 bays. Commercial (store). Commercial vernacular. Ca. 1914, remodelled 1965. Builder: C. W. Pollard.

1716: brick (stretcher bond); 2 stories; shed roof; 2 bays-1st floor, 3 bays-2nd floor. Commercial (store). Commercial vernacular. Ca. 1914, remodelled 1963. Architect: D. Wiley Anderson.

1717-19-21: See appendix (Continuation Sheet #51)

1718: brick (stretcher bond); 2 stories; parapet roof; 3 bays. Commercial (office and store). Commercial vernacular. Ca. 1915. Builder: James Fox and Sons.


1720-22-24-26: brick (stretcher bond); 2 stories; parapet roof; 8 bays, 4 divisions. Commercial (store). Commercial vernacular. 1915. Builder: James Fox and Sons.

1725-29: See appendix (Continuation Sheet #51)

1731 ("McCurdy House" - Reliable furniture): brick (stretcher bond); 3 stories; gable roof (standing-seam metal); 2, gable dormers; 4 bays-1st floor, 3 bays-2nd and 3rc floors. Commercial (office and store). Greek Revival. 1845, ca. 1973 remodelled storefront. Builder: Neil McCurdy.

National Register of Historic Places Inventory—Nomination Form

Shockoe Valley and Tobacco Row Historic District, Richmond, VA Continuation sheet #28 Item number 7



Page

7. DESCRIPTION -- Inventory (continued)

MAIN STREET (continued)

1800 Block

Southeast corner 18th and E. Main streets: parking lot.

1800-02: brick (7-course American bond); 2 stories; flat roof; 3 bays. Commercial (store). Greek Revival. Ca. 1835.

1804-06: brick (7-course American bond); 2 stories; shed roof; 6 bays - 1st floor, 4 bays - 2nd floor, 2 divisions. Commercial (store). Late Greek Revival with added storefronts. Ca. 1845.

1808-1810: brick (stretcher bond); 2 stories; shed roof; 7 bays-1st floor, 5 bays-2nd floor. Commercial (store) with residence above. Transitional Greek to Italianate. Ca. 1845.

1811-13: brick (stretcher bond); 3 stories; shed roof; 3 bays-1st floor, 2 bays-2nd floor. Commercial (office and store). Commercial vernacular. Ca. 1910.

1812-1814: brick (stretcher bond); 2 stories; shed roof; 5 bays-1st floor, 6 bays-2nd floor, 2 major divisions. Commercial (store). Commercial vernacular. Ca. 1922.

1816: brick (stretcher bond); 3 stories; shed roof; 3 bays. Commercial (office and store). Commercial Italianate. Ca. 1870.

1818: brick (stretcher bond); 2 stories; shed roof; 4 bays-1st floor, 3 bays-2nd floor. Commercial (store) with residence above. Commercial vernacular. Ca. 1915. Architect/builder: A. D. Hunt.

1820-22: vacant lot.

1821-23-23½-25: brick (stretcher bond); 2 stories; shed roof; 8 bays-1st floor, 9 bays-2nd floor. Commercial (store) with residence above. Commercial vernacular. Ca. 1911, ca. 1975 storefronts remodelled on 1823-25. Builder: Capt. L. Jenkins.

1900 Block

1900: brick (stretcher bond); 3 stories; shed roof; 3 bays. Commercial warehouse. Commercial vernacular. Ca. 1910. Architect: Anderson & Skinner, builder: R. H. Walton.

1902: brick (stretcher bond); 2 stories; parapet roof; 4 bays-1st floor, 3 bays-2nd floor. Commercial (store) with residence above. Commercial vernacular. Ca. 1915.

1904-06: brick (stretcher bond); 2 stories; parapet roof; 8 bays-1st floor, 6 bays-2nd floor. Commercial (office and store). Art Deco influence. Ca. 1913. Architect: A. F. Hunt, builder: W. S. Quarles.

National Register of Historic Places Inventory—Nomination Form

Shockoe Valley and Tobacco Row Historic District, Richmond, VA

Continuation sheet

Item number

Page

For HCRS use ont

received

date entered

7. DESCRIPTION -- Inventory (continued)

MAIN STREET (continued)

1900 Block (continued)

1907-1915-1923: brick (possibly 5-course American bond, but heavily painted); 3 stories; gable roof; 13 bays. Industrial. Industrial vernacular. Ca. 1910.

1908: brick (6-course American bond), 2 stories; shed roof; 3 bays. Commercial (store) with residence above. Commercial vernacular. Ca. 1920.

1910: vacant lot.

1912: brick (stretcher bond); 2 stories; shed roof; 4 bays. Commercial (store). Commercial vernacular. Ca. 1913. Architect: A. Hunt, builder: G. J. Hunt.

1914: brick (6-course American bond); 1½ stories; gambrel roof (slate); 1, gable dormer; 2 bays; 1-story, 1-bay (east side) porch. Museum. Colonial Revival remodelling Ca. 1920, remodelled ca. 1950.

1916 (Old Stone House): stone (random rubble); 1½ stories; gable roof (wood shingle); 3, gable dormers; 3 bays. Detached house. Residential vernacular (colonial) After 1737. Architect: possibly Jacob Ege.

1918: brick (6-course American bond); 2½ stories; shed roof (slate); 2 bays. Museum. Builder's vernacular. Ca. 1928.

 \mathcal{L}_{U}

1920-22: parking lot for Poe Museum.

2000 Block


2000: parking lot.

2005: brick (stretcher bond); 1 story; flat roof; 7 bays. Gas station (old). Commercial. Commercial vernacular. Ca. 1915.

2010: brick (stretcher bond); 1 story; flat roof; 5 bays (structural). Commercial (office). Commercial vernacular. 1928 - with 3 bays, ca. 1969 - 2 east bays.


2016 (#2 Engine House): brick (stretcher bond); 2½ stories; hipped roof-front section, gambrel roof-rear section (slate); 1, gable dormer; 2 bays-1st floor, 1 bay-2nd floor. Fire station. 1899.

2025: brick (3-course American bond with Flemish bond); 2 stories; 3 bays, 1-bay addition to west; 1-story, 1-bay (center) porch. Government. Builder's vernacular. Ca. 1950.



National Register of Historic Places Inventory—Nomination Form

Shockoe Valley and Tobacco Row Historic District, Richmond, VA Continuation sheet #30 Item number 7



Page

7. DESCRIPTION -- Inventory (continued)

MAIN STREET (continued)

2100 Block

2100: brick (stretcher bond); 2 stories; shed roof; 3 bays. Commercial (store) with residence above. Commercial vernacular. Ca. 1908.

2101-11: brick (5-course American bond); 1 story; shed roof; 10 bays. Industrial. Industrial vernacular. 1890 - date plaque.

2102: brick (stretcher bond); 2 stories; parapet roof; 4 bays-1st floor, 3 bays-2nd floor. Commercial (office) with residence above. Commercial vernacular. Ca. 1920

2104: brick (stretcher bond); 2 stories; parapet roof; 3 bays. Commercial (store) with residence above. Commercial vernacular. 1916 - date stone. Builder: A. C. Houston & Son.

2106-08: brick (stretcher bond); 1 story; parapet roof; 5 bays. Industrial. Commercial vernacular. Ca. 1911, storefront altered 1959. Builder: J. E. Collins.

2110-12: brick (stretcher bond); 2 stories; shed roof; 7 bays-1st floor, 6 bays-2nd floor. Commercial (store)-formerly, church-now. Commercial vernacular. Ca. 1912, storefront altered ca. 1959. Builder: Stagg & Son.

2113: brick (stretcher bond); 1 story; flat roof; 3 bays. Commercial. Commercial vernacular. Ca. 1925.

2114: brick (stretcher bond); 2½ stories; gable roof (standing-seam metal); 1 dormer; 3 bays-1st floor, 2 bays-2nd floor. Detached town house-formerly (possibly ½ of double house), commercial (office)-now. Greek Revival with added storefront. Ca. 1853.

2116-18: brick (7-course American bond); 2 stories; shed roof; 4 bays. Commercial (office). Commercial vernacular. Ca. 1925.

2117: brick (stretcher bond); 2½ stories; hipped, truncated roof (slate); 1, hipped dormer, also one on either side; 5 bays; 1-story, 1-bay (center) porch. Government. Colonial Revival. 1892.

2120-2128: parking lot.


2127 (Henrico County Courthouse): brick (stretcher bond); 3½ stories; flat and pyramidal roof (slate on pavilions, not visible on flat center bay; 1, gable dormer; 5 bays, 3 major bays. Government. Late Romanesque Revival. 1896. Architect/builder: Carl Ruehrmund.

2127, South Annex, rear of Henrico County Courthouse: brick (6-course American bond); 2 stories with basement; flat roof; 4 bays. Government office. Builder's vernacular. 1920.

National Register of Historic Places Inventory—Nomination Form

Shockoe Valley and Tobacco Row Historic District, Richmond, VA

Continuation sheet #31 Item number 7



Page

7. DESCRIPTION -- Inventory (continued)

MAIN STREET (continued)

2200 Block

2200-04: brick (stretcher bond); 2 stories; shed roof; 6 bays. Commercial (store) with residence above. Remodelled Greek Revival. Ca. 1830.

2201-5: brick (6-course American bond); 2 stories; 5 bays. Industrial. Art Decoinfluenced. Ca. 1921.

2206: brick (6-course American bond); 2 stories; shed roof; 3 bays-1st floor, 2 bays-2nd floor. Commercial (office and store). Commercial vernacular Italianate. Facade ca. 1885.

2207-13: brick (5-course American bond); 1 story; flat roof; 8 bays. Industrial. Industrial vernacular. Ca. 1955.

2219, (2215-17 addition): brick (stretcher bond), wood storefront-1st story; 2 stories; shed roof; 4 bays-1st floor, 3 bays-2nd floor. Commercial (office) and warehouse. Commercial Italianate. Ca. 1880.

2220: brick (5-course American bond); 2 stories; flat roof; 11 bays. Commercial (office) and industrial. Commercial vernacular. Ca. 1950.

2221: vacant lot.

2223: brick; 3 stories; flat roof; 2 bays-1st floor, 3 bays-2nd and 3rd floors. Commercial (office) and shop. Commercial Italianate with remodelled storefront. Ca. 1885, storefront ca. 1935.

√ 2225-27: parking lot.

2300 Block


2300-02: brick (stretcher bond), 2 stories, gable roof (standing-seam metal); 4 bays. Commercial (office)-now, possibly double town house converted to commercial use ca. 1840. Late Greek Revival converted to Commercial Italianate. Ca. 1840-43. Builder: Joseph Woodson.

2301-5: brick (7-course American bond with Flemish bond on 1st story and basement and 8-course American on 2nd story); 2 stories plus basement; flat roof; 6 bays. Industrial (office-1st story). Industrial vernacular. Ca. 1917 with ca. 1930 2nd-story addition.

2304-2308: brick (Flemish bond row with 8-, 9-, and 10-course American bond); 2 stories; shed roof; 9 bays-1st floor (3 major sections), 6 bays-2nd floor. Commercial (office-now and store-formerly). Commercial Italianate. Ca. 1870, 1979 renovation.

National Register of Historic Places Inventory—Nomination Form

Shockoe Valley and Tobacco Row Historic District, Richmond, VA Continuation sheet #32 Item number 7



Page

7. DESCRIPTION -- Inventory (continued)

MAIN STREET (continued)

2300 Block (continued)

2310-12: brick (7- and 8-course American bond); 1 story; parapet roof; 4 bays. Industrial. Commercial vernacular. Ca. 1857. Builder: Joseph Forstman.

2314: brick (stretcher bond) and concrete block; 1 story; gable roof (metal); 2 bays. Industrial. Industrial vernacular. 1974.*

2318-32: brick (6-course American bond); 1 story; shed roof; 10 bays. Industrial. Industrial vernacular. Ca. 1919.

2323: brick (5-course American bond with Flemish bond); 2 stories plus basement; flat roof; 8 bays. Industrial. Industrial vernacular. Ca. 1917. Architect: W. Duncan Lee.

2400 Block

2400-2406: brick (7-course American bond); 2 stories; shed roof; 9 bays. Industrial. Industrial vernacular. Ca. 1880.

2401-03: brick (5-course American bond); 2 stories; flat roof; 5 bays. Commercial (office). 1956.

2408-10: parking lot.

2412: brick (stretcher bond); 2½ stories; gable roof (standing-seam metal); 2, gable dormers; 4 bays-1st floor, 3 bays-2nd floor. Town house converted to store with residence above. Vernacular Greek Revival with alterations. Ca. 1869.

2414: brick (8-course American bond); 2½ stories; gable roof (standing-seam metal); 2, gable dormers; 4 bays-1st floor, 3 bays-2nd floor. Town house converted to store with residence above. Builder's alteration of vernacular Greek Revival. Ca. 1869.

2416-2418: vacant lot,

2419-29: parking lot.

2420: brick (6-course American bond); 2 stories; shed roof; 3 bays. Apartments-duplex Builder's vernacular. Ca. 1930.

2422-24: brick (stretcher bond); 3 stories; shed roof; 7 bays-1st floor (2 major sections); 6 bays-2nd and 3rd floors. Commercial (store) with residence above. Commercial Italianate. Ca. 1875.

National Register of Historic Places Inventory—Nomination Form

Shockoe Valley and Tobacco Row Historic District, Richmond, VA

Continuation sheet #33

Item number 7

For HCRS use only received is date entered

Page

7. DESCRIPTION -- Inventory (continued)

MAIN STREET (continued)

2500 Block

2501: brick (stretcher bond); 3 stories; gable roof; 10 bays plus 7-bay extension. Industrial warehouse. Industrial vernacular. Ca. 1900.

2506: enameled steel panels over brick; 1 story; flat roof; 3 bays. Gas station. International vernacular. Ca. 1930.*

2515: brick (6-course American bond); 3 stories; shed roof; 8 bays. Industrial warehouse. Builder's Industrial vernacular. Ca. 1900.

Northwest corner of 26th and E. Main streets, east of 2500 E. Main Street: vacant lot

2600 Block

2600: brick (5- and 6-course American bond); l story; flat roof; 6 bays. Gas station. Builder's vernacular. Ca. 1930.

East of 2600 E. Main, north side: parking lot.

2603: brick (6-course American bond); 1 story; shed roof; 3 bays. Commercial (restaurant). Builder's vernacular. Ca. 1950.

2613: brick (stretcher bond); 2 stories; shed roof; 3 bays. Commercial (store) with residence above. Commercial Italianate. Ca. 1890.

2615: brick (stretcher bond); 3 stories; flat roof; 4 bays-1st floor, 3 bays-2nd and 3rd floors. Commercial with residential 2nd and 3rd floors. Commercial Italianate. Ca. 1880.

2700 Block

South side of E. Main Street between 2709 E. Main and parking lot east of 2615 E. Main: parking lot.

North side of E. Main Street, west of 2708: vacant lot.

2708: brick; 14 stories; gable roof (slate); 4 bays. Gas station. Builder's vernacular. Ca. 1930s.

2709: cement stucco over brick; 2 stories; shed roof; 3 bays. Commercial (store). Commercial Italianate. Ca. 1880.

2711: brick (3-, 4-, and 5-course American bond); 2 stories; shed roof; 4 bays-1st floor, 3 bays-2nd floor. Commercial (office and store). Commercial vernacular. Ca. 1939.

(See Continuation Sheet #34)

National Register of Historic Places Inventory—Nomination Form

Shockoe Valley and Tobacco Row Historic District, Richmond, VA

Continuation sheet #34

Item number 7

For HCRS use only:
received
date entered

Page

7. DESCRIPTION -- Inventory (continued)

MAIN STREET (continued)

2700 Block (continued)

Southwest corner of E. Main and Pear streets: parking lot.

2800 Block

2805: concrete block; 1 story; flat roof; 1 bay. Gas station. Builder's vernacular. Ca. 1960.

2821: corrugated metal ("board-and-batten" style); l story, gable roof (standing-seam metal); l bay. Commercial (office). Builder's vernacular. Ca. 1975.

2823: brick (5-course American bond); 4 stories; gable roof; 3 bays-1st floor, 2 bays-2nd-4th floors. Industrial. Industrial vernacular. Ca. 1850, facade altered ca. 1940.

EAST MARSHALL STREET

1600 Block

1600: poured concrete over concrete block; 1 story; flat roof; 3 bays. Commercial storage outbuilding. Builder's vernacular. Ca. 1950.

Rear of 1600 E. Marshall (1 of 5 buildings): corrugated metal and steel; 1 story; flat roof; 6 bays. Mobile home. Trailer vernacular. Ca. 1965.

Rear of 1600 E. Marshall (2 of 5 buildings): corrugated metal and steel; 1 story; shed roof (metal); 5 bays. Garage. Builder's vernacular. Ca. 1975.

Rear of 1600 E. Marshall (3 of 5 buildings): corrugated metal and wood; 1 story; shed roof (metal); 6 bays. Garage. Builder's vernacular. Ca. 1960.

Rear of 1600 E. Marshall (4 of 5 buildings): brick (6-course American bond with variations); 1 story; flat roof (standing-seam metal); 2 bays. Private garage. Builder's vernacular. Ca. 1930.


Rear of 1600 E. Marshall (5 of 5 buildings): Complex of 2 large cylindrical storage towers and 4 cylindrical storage drums elevated on concrete supports. Also with apparatus necessary to fill oil trucks. All set on concrete podium. Asphalt lot to north.

On north/south alley between N. 16th and N. 17th streets, E. Marshall Street, and Expressway, east side: brick (6-course American bond); 1 story, shed roof; 2 bays. Outbuilding. Vernacular. Ca. 1930.

National Register of Historic Places Inventory—Nomination Form

Shockoe Valley and Tobacco Row Historic District, Richmond, VA

Continuation sheet #35 Item number 7



Page

7. DESCRIPTION -- Inventory (continued)

EAST MARSHALL STREET (continued)

1600 Block (continued)

South side between 16th and 17th streets, in State parking lot #5 north: large metal crane with cog-wheel pulley system set on concrete base. Set in vacant railroad lot with railroad spur to east and elevated trestle to west.

Center of north side: vacant lot.

1700 Block

1703: concrete block; 1 story; flat roof; 5 bays. Industrial. Builder's vernacular 1954.

PEAR STREET

100-104

NW corner of Pear & Dock Streets: brick (6-course American bond); 1 story; shed roof; 2 bays. Industrial warehouse. Industrial vernacular. Ca. 1890.

SW corner of East Cary & Pear: brick (6-course American bond); 1 story; shed roof (corrugated metal on west half of building); 3 bays. Industrial warehouse. Industrial vernacular. Ca. 1890.

NORTH 15th STREET

East side of N. 15th between East Main Street & East Franklin: parking lot.

SOUTH 15th STREET

00 Block

- 3: brick (stretcher bond); 3 stories; shed roof; 4 bays in 2 sections. Industrial print shop. Commercial vernacular. Ca. 1920.
- 5: brick (stretcher bond); 3 stories; shed roof; 3 bays on 2nd and 3rd floors and 4 bays on 1st floor. Commercial office above store. Commercial vernacular. Ca. 191

NORTH 17th STREET

North 17th Street Market: metal pipe; 1 story; shed roof (corrugated metal); 29 bays. Outdoor market. Ca. 1962.

(See Continuation Sheet #36)

08 - 100,100**4-0018** FKS:10781504

United States Department of the Interior National Park Service

National Register of Historic Places Inventory—Nomination Form

Shockoe Valley and Tobacco Row Historic District, Richmond, VA

Continuation sheet #36 Item number 7



Page

7. DESCRIPTION -- Inventory (continued)

NORTH 17th STREET (continued)

00 Block

3: brick (Flemish bond); 3 stories; shed roof; 3 bays. Commercial office above store. Commercial vernacular. Ca. 1833.

5-7: brick (6-course American bond); 1 story; shed roof; 2 structural bays.

Commercial (store). Commercial vernacular. Ca. 1910.

9-11: brick (stretcher bond); 1 story; shed roof; 2 bays. Commercial (store). Commercial vernacular. Ca. 1960 store front on ca. 1950 building.

13: brick (stretcher bond); 2 stories; shed roof; 2 bays. Commercial office above store. Commercial Italianate vernacular. Ca. 1890.

14 & 16: brick (stretcher bond); 1 story; fake mansard roof (slate on mansard); 5 bays with a small sidelight bay at the far N and S. Commercial (store). Commercial vernacular. Ca. 1960 store front on S 3 bays on ca. 1915 building.

15: layered concrete over brick; 2 stories; shed roof; 3 bays. Commercial office over store. Commercial Italianate vernacular. Ca. 1869 (J. Zehmer), ca. 1885, ca. 1961 lower facade.

17-17-19: brick (6-7-course American bond); 2 stories; shed roof; 3 bays. Commercial office above store. Commercial vernacular. Ca. 1925.

18-20: brick (stretcher bond); 2 stories; shed roof; 2 bays. Commercial office above store. Commercial vernacular. Ca. 1911.

21: brick (stretcher bond); 2 stories; shed roof; 3 bays. Commercial (restaurant).
Commercial vernacular. Ca. 1910; remodeled 1970.

23-27: See appendix (Continuation Sheet #51)
22-24: brick (stretcher bond); 3 stories; shed roof; 6 bays in 2 major divisions.
Formerly double house; now residential above commercial (store). Greek Revival vernacular. Ca. 1840.

29: brick (stretcher bond); 3 stories; shed roof; 4 bays on 1st floor and 3 bays on 2nd & 3rd floors. Rooming house above commercial (store). Italianate vernacular. Ca. 1875.

100 Block

W side of 100 Block: parking lot.

NPS Form 10-900-a

United States Department of the InteriorNational Park Service

National Register of Historic Places Inventory—Nomination Form

Shockoe Valley and Tobacco Row Historic District, Richmond, VA Continuation sheet #37 Item number 7



Page

7. DESCRIPTION -- Inventory (continued)

NORTH 17th STREET (continued)

100 Block (continued)

101: brick (stretcher bond); 2 stories; shed roof; 3 bays. Commercial office above store. Commercial vernacular. Ca. 1911.

103 & 105: brick (stretcher bond); 2 stories; shed roof; 6 bays in 2 major divisions (N and S). Commercial office above store. Commercial vernacular. Ca. 1911.

107: brick (stretcher bond); 2 stories; shed roof; 3 bays. Commercial office above store. Commercial vernacular. Ca. 1912.

109-111: brick (stretcher bond); 2 stories; shed roof; 3 bays on 1st floor and 4 bays on 2nd floor. Commercial store (formerly) with office above, now residential above store. Commercial vernacular. Ca. 1912.

113, 115, 117, 119: vacant lots.

121-123: concrete block; 1 story; flat roof; 2 bays. Industrial bakery. Builders vernacular. Ca. 1980.*

125: stucco; l story; flat roof; 2 bays. Industrial (bakery). Plain commercial vernacular. Ca. 1965.

127: brick (stretcher bond); 2 stories; shed roof; 2 bays. Formerly commercial office above store; now industrial (bakery). Commercial vernacular. Ca. 1900.

129: brick (stretcher bond); 2 stories; shed roof; 3 bays on 1st floor and 2 bays on 2nd floor. Formerly commercial office above store; now industrial (bakery). Commercial vernacular. Ca. 1900.

SE corner N. 17th & East Grace Street: vacant lot.

200 Block

N. 17th Street between E. Grace and E. Broad, East side (Seabrooks Warehouse Site): brick (5-course American bond); 1 story; gable roof (standing seam metal); 2 bays. Utility shed. Builders vernacular. Ca. 1920.

200: brick (stretcher bond); 2 stories; flat roof; 2 bays on 1st floor and 3 bays on 2nd floor. Commercial office above store. Commercial vernacular. Ca. 1880.

NPS Form 10-900-a (7-81)

United States Department of the InteriorNational Park Service

National Register of Historic Places Inventory—Nomination Form

Shockoe Valley and Tobacco Row Historic District, Richmond, VA Continuation sheet #38 Item number 7



Page

7. DESCRIPTION -- Inventory (continued)

NORTH 17th STREET (continued)

200 Block (continued)

202: brick (stretcher bond); 2 stories; shed roof; 2 bays. Commercial office above store. Commercial Italianate vernacular. Ca. 1880.

204 to SW corner of E. Broad & N. 17th Street: vacant lot.

SE corner N. 17th & E. Broad Street: vacant lot.

300 Block

300: See appendix (Continuation Sheet #52)

301: stucco over brick; 1 story; parapet roof; 4 bays. Gas station. Commercial vernacular. Ca. 1930.

307: brick (9-course American bond); 4 stories; flat roof; 3 structural bays and 4 bays on 1st floor. Industrial. Industrial vernacular. Ca. 1925.

127 1

317: brick (6-course American bond and concrete); 4 stories; parapet roof; 9 bays. Industrial vernacular. Ca. 1910.

329-331: brick (stretcher bond); originally 3 stories plus basement, now 4 stories plus basement; flat roof; 3 bays. Industrial. Industrial vernacular. Ca. 1920.

400 Block

400: brick (6-course American bond); 2 stories; shed roof; 20 bays. Railroad. Industrial vernacular. Ca. 1920.

401: brick (6-course American bond); 1 story; flat roof; 9 structural bays and 6 bays. Industrial. Industrial vernacular. Ea. 1925.

415-21: brick (5-course American bond); 2 stories; flat roof; 8 bays on 1st floor and 13 bays on 2nd floor. Industrial. Industrial vernacular. Ca. 1915.

SOUTH 17th STREET

00 Block

12 & 14: brick (6-course American bond); 6 stories; flat roof; 4 bays. Industrial (warehouse). Industrial vernacular. Ca. 1914.

13: brick (6-course American bond); 2 stories; flat roof; 2 bays. Commercial office above store. Commercial vernacular. Ca. 1930.


(See Continuation Sheet #39)

United States Department of the Interior National Park Service

National Register of Historic Places Inventory—Nomination Form

Shockoe Valley and Tobacco Row Historic District, Richmond, VA

Continuation sheet #39 Item number 7



Page

7. DESCRIPTION -- Inventory (continued)

00 Block

15-17: brick (6-course American bond); 2 stories; flat roof; 2 bays. Industrial warehouse. Commercial vernacular. Ca. 1930.

16-20: brick (7-course American bond); 2 stories; flat roof; 9 bays in 3 major divisions. Commercial office above store. Commercial vernacular. Ca. 1900.

 \mathcal{N}^{N} Lot S of #17: parking lot.

NORTH 18th STREET

00 Block

2-2½: brick (stretcher bond); 2 stories; shed roof; 5 bays on 1st floor and 4 bays on 2nd floor in 2 major divisions. Commercial office above store. Commercial vernacular. Ca. 1914.

4-4½: brick (stretcher bond); 2 stories; shed roof; 6 bays on 1st floor and 4 bays on 2nd floor in 2 major divisions on 1st floor. Commercial office above store. Commercial vernacular. Ca. 1912.

3: brick (stretcher bond); 1 story; shed roof; 2 bays. Commercial (store). Commercial vernacular. Ca. 1915.

6-6½: brick (stretcher bond); 3 stories; shed roof; 3 bays on 1st floor and 4 bays on 2nd/3rd floors. Commercial office above store. Commercial Italianate vernacular. Ca. 1890.

8 & 10: brick (6-course American bond); 2 stories; shed roof; 6 bays on 1st floor and 4 bays on 2nd floor. Commercial office above store. Commercial vernacular. Ca. 1960 facade on ca. 1913 building.

9-11: pre-cast concrete over brick; 1 story; flat roof; 4 bays. Commercial (store). Builders vernacular. Facade ca. 1965.

12½ & 14: brick (stretcher bond); 2 stories; shed roof; 6 bays in 3 major divisions. Commercial office above store. Commercial vernacular. Ca. 1958 store front; ca. 1913 building.

13-15: pre-cast concrete facing over brick; 3 stories; shed roof; 4 bays. Commercial (store). Builders remodeling. Facade ca. 1965.

16: brick (Flemish bond); 2 stories; flat roof; 3 bays. Commercial office above store. Commercial vernacular. Ca. 1913; front altered ca. 1973-75.

United States Department of the Interior National Park Service

National Register of Historic Places Inventory—Nomination Form

Shockoe Valley and Tobacco Row Historic District, Richmond, VA

Continuation sheet #40

Hern number 7



Page

7. DESCRIPTION -- Inventory (continued)

NORTH 18th STREET (continued)

00 Block (continued)

17: vacant lot.

19: brick (5-course American bond); 2 stories; shed roof; 4 bays on 1st floor and 3 bays on 2nd floor. Commercial office above store. Commercial vernacular.

Ca. 1925.

100 Block

101-109: brick (stretcher bond); 3 stories; shed roof; 5 bays on 1st floor and 12 bays on 2nd/3rd floors in 5 major divisions. Commercial office above store. Commercial Italianate vernacular. Ca. 1878.

 $_{
m N}$ Lot for 108.

104 & 106: brick (stretcher bond) with wood store front; 1 story; flat roof; 7 bays. Commercial (store). Commercial vernacular. Ca. 1905.

110: brick (stretcher bond); 2 stories; flat roof; 2 bays. Commercial office above wholesale store. Commercial vernacular. Ca. 1959.

Between 110 & 120: parking lot.

111-13: brick (stretcher bond); 2 stories; shed roof; 6 bays on 1st floor and 5 bays on 2nd floor. Commercial office above store. Commercial Italianate. Ca. 1875.

115: brick (stretcher bond); 2 stories; shed roof; 4 bays. Commercial office above store. Commercial vernacular. Ca. 1910.

117: brick (5-course American bond with Flemish bond row); 1 story; flat roof; 3 bays. Garage. Builders vernacular. Ca. 1915.

119: concrete block; 1 story; shed with fake mansard roof (metal mansard in horizontal strips); 1 bay. Garage. Builders vernacular. Ca. 1925 with ca. 1960 facade.

120: brick (stretcher bond); 1 story; shed roof; 1 bay. Commercial warehouse. Commercial vernacular. Ca. 1970 brick veneer facing on ca. 1910 building.

121: brick (storefront infill stretcher bond with 6-course American bond above storefront cornice, original); 1 story; shed roof; 3 bays. Commercial (store). Commercial vernacular. Ca. 1920; altered ca. 1971.

EXP. 10/31/84

United States Department of the Interior National Park Service

National Register of Historic Places Inventory—Nomination Form

Shockoe Valley and Tobacco Row Historic District, Richmond, VA #41 Continuation sheet Item number



Page

DESCRIPTION -- Inventory (continued)

NORTH 18th STREET (continued)

100 Block (continued)

123: brick sides and concrete block facade; 1 story; shed roof; 2 bays. Garage. Builders remodeling. Facade ca. 1972.

125-27: brick (stretcher bond); I story; shed roof; 2 bays. Commercial (store). Commercial vernacular. Ca. 1920.

122-28: brick (stretcher bond); 1 story; shed roof; 4 bays. Commercial (office) and warehouse. Commercial vernacular. Ca. 1920.

200 Block

200: corrugated metal (vertical ribbing); 1 story; gable roof (standing seam metal); l bay. Utility shed. Ca. 1968 A

201: corrugated metal (vertical ribbing); l story; gable roof (standing seam metal); l long bay. Garage. Industrial vernacular. Ca. 1970.⊁

209: brick (6-course American bond); 1 story; shed roof; 4 bays. Service garage. Builders vernacular. Ca. 1950.

211: See appendix (Continuation Sheet #52)
213: brick (stretcher bond); 2½ stories; gable roof (standing seam metal); 1 pedimented dormer; 3 bays. 1-story porch with 3 bays, Queen Anne detailing: turned posts and open lattice frieze; frieze lattice missing from S 2 bays; plain, flat balusters, porch elevated on brick piers from street level, flight of wood stairs; porch is later addition. Detached town house. Greek Revival. Ca. 1850.

214-16: vacant lot.

215: vacant lot.

300 Block

314: brick (stretcher bond); 1 story; shed roof; 3 bays. Commercial office above work Commercial vernacular. Ca. 1905. Shop.

320; brick (stretcher bond); 2 stories; parapet roof; 3 bays. Industrial warehouse with office. Industrial vernacular. Ca. 1910.

324: brick (stretcher bond); 2 stories; flat roof; 1 bay on 1st floor and 3 bays on 2nd floor. Garage with office above. Builders vernacular. Ca. 1968.

(See Continuation Sheet #42)

United States Department of the Interior National Park Service

National Register of Historic Places Inventory—Nomination Form

Shockoe Valley and Tobacco Row Historic District, Richmond, VA Continuation sheet #42 Item number 7



Page

7. DESCRIPTION -- Inventory (continued)

NORTH 18th STREET (continued)

300 Block (continued)

328-334: brick (5-course Amèrican bond); l story; flat roof; 5 bays. Commercial office with warehouse below. Commercial vernacular. Ca. 1930.

400 Block

406-12 (NW corner N. 18th Street & E. Marshall Street): brick (5-course American bond); openings on 1st story only, probably 5 stories inside; flat roof; 7 structural bays and 3 openings on 1st floor. Industrial. Industrial vernacular. Ca. 1925.

SE of 423 (Church Hill Tunnel),

423: brick (6-course American bond); 4 stories; gable roof; ll bays. Industrial warehouse. Industrial vernacular. Ca. 1915.

429: brick (5-course American bond); 5 stories; flat, parapet roof; 5 bays. Industrial warehouse. Industrial vernacular. Ca. 1910.

431: brick (6-course American bond); 4 stories; shed roof; 3 bays. Industrial. Industrial vernacular. Ca. 1910.

SOUTH 18th STREET

00 Block

2-4-6: brick (6-course American bond); 1 story; shed roof; 3 bays. Commercial (store). Commercial vernacular. Ca. 1915.

8: brick (5-course American bond) and stucco (concrete), stucco over brick; 1 story; flat roof; 4 bays. Commercial warehouse. Commercial vernacular. Ca. 1920.

11-15: brick (7-course American bond); 3 stories; shed roof; 8 bays originally, 3 divisions. Industrial warehouse. Industrial vernacular. Ca. 1900.

20-28: brick (5-course American bond); 5 stories; flat roof; 13 bays. Industrial warehouse. Industrial vernacular. Ca. 1910.

NE corner of S. 18th Street & E. Cary Street: parking lot.


(See Continuation Sheet #43)

GNA NO. 1024-0018 ZMP. 10781184

United States Department of the InteriorNational Park Service

National Register of Historic Places Inventory—Nomination Form

Shockoe Valley and Tobacco Row Historic District, Richmond, VA Continuation sheet #43 | Item number 7



Page

7. DESCRIPTION -- Inventory (continued)

SOUTH 18th STREET (continued)

100 Block

330

101: brick (5-course American bond); 3 stories; gable roof; 7 bays on 1st floor and 5 bays on 2nd and 3rd floors. Commercial warehouse. Commercial vernacular. Ca. 1910.

NORTH 19th STREET

00 Block

NW corner of N. 19th Street and E. Main Street: vacant lot.

- 1, 14, 3: brick (stretcher bond) and concrete block; 3 stories; flat roof; 5 bays on 1st floor in 4 major divisions and 8 bays on 2nd and 3rd floors. Commercial warehouse. Industrial Colonial Revival. Ca. 1908.
- 6: concrete block; 2 stories; flat roof; 4 bays on 1st floor and 3 bays on 2nd floor. Industrial warehouse. Builders vernacular. Ca. 1955.
- 7-11: brick (6-course American bond), brick piers support wood lintel; 1 story; flat roof; 4 bays. Garage. Builders vernacular. Ca. 1940.
- 8-12: brick (stretcher bond on 1-2-story new facade and 5-course American bond on upper section old facade); 1 and 3 stories, (L-shaped in elevation); shed roof on S section and parapet, flat roof on N section; 5 bays on 1st floor and 3 bays on 2nd/3rd floors. Industrial. Builders vernacular. Ca. 1853; new facade ca. 1971 (1st/2nd floors).
- 14: brick (5-course American bond); 1 story; flat roof; 1 bay. Commercial (store). Builders commercial vernacular. Ca. 1940.
- 15: brick (stretcher bond); 3 stories; flat roof; 5 bays. Industrial warehouse. Industrial vernacular. Ca. Ante-bellum.
- 19: brick (7-course American bond); 2½ stories; gable roof (standing seam metal); 7 bays. Industrial warehouse. Industrial vernacular. Ca. Ante-bellum.
- 23: brick (7-course American bond); 2 stories; parapet and gable roof (standing seam metal); 5 bays. Industrial warehouse. Industrial vernacular. Ca. Ante-bellum.

100 Block


102: brick (6-course American bond); 1-story S section and 2-story N section office; flat roof; 5 bays. Industrial warehouse. Builders vernacular. Ca. 1950.

NPS Form 10-900-a (7-31)

United States Department of the Interior National Park Service

National Register of Historic Places Inventory—Nomination Form

Shockoe Valley and Tobacco Row Historic District, Richmond, VA Continuation sheet #44 Item number 7



Page

7. DESCRIPTION -- Inventory (continued)

NORTH 19th STREET (continued)

100 Block (continued)

104: brick (6-course American bond); 2 stories; flat roof; 3 bays. Warehouse currently. Gothic Revival. Ca. 1900.

 $\eta^{\lambda V}$ 108-18: vacant lot.

115: concrete block; l story; gable roof (standing seam metal); 2 bays. Industrial warehouse. Builders vernacular. Ca. 1955.

117: concrete block; I story; flat roof; 3 bays. Service station. Builders vernacular. Ca. 1956.

200 Block

201: overgrown lot.

202: brick (stretcher bond); 2 stories with elevated basement; shed roof; 3 bays. 1-story, 3-bay porch with slender cast iron columns joining wrought-iron balustrades, brackets and frieze, hipped metal roof with cresting elevated on brick end piers and metal pole (center) stone flight of stairs with stone stringer. Detached town house. Italianate. Ca. 1855.

204: brick (stretcher bond); 2 stories; shed roof; 3 bays. 1-story, 3-bay porch of wood with turned posts and decorative balustrade; some replaced with cross bracing, plain wood box cornice and frieze, new 3-step brick stair; porch raised slightly on piers; hipped metal roof. Detached town house. Builders Italianate. Ca. 1875.

205 (Pace-King House): brick (stretcher bond); 2 stories; hipped roof; 3 bays. l-story, 3-bay porch with decorative Italianate ironwork, center bay slightly projecting, flat roof. Detached house. Italianate. Ca. 1860.

205 (rear of Pace-King House): brick (stretcher bond); 2 stories; flat roof; 6 bays. 2-story, 4-bay porch with gallery across entire facade, square columns on stone sill support plain frieze over 2nd floor joists, reflected end pilasters, 2nd story plain rectangular balustrade, cornice has full entablature; stairs to 2nd story along E side. Outbuilding. Builders vernacular. Ca. 1870.

205 (rear of Pace-King House): brick (6-course American bond); 2 stories on split grade; flat roof; 4 bays. Garage. Builders vernacular. Ca. 1860 with alterations.

United States Department of the Interior National Park Service

National Register of Historic Places Inventory—Nomination Form

Shockoe Valley and Tobacco Row Historic District, Richmond, VA Continuation sheet #45 Item number 7



Page

7. DESCRIPTION -- Inventory (continued)

NORTH 19th STREET (continued)

200 Block (continued)

206: brick (stretcher bond); 2 stories; shed roof; 3 bays. 1-story, 3-bay plain Colonial Revival wood porch with attenuated wood columns and diagonally braced balustrades, hipped asphalt roof with cresting at corners and over N column; single granite step. Detached town house. Builders Italianate. Ca. 1875.

208: brick (stretcher bond); 2½ stories; gable roof (standing seam metal); 3 bays. l-story, l-side-bay porch with cement 5-step stair to cement platform; remainder of porch missing; ghost on brickwork. Double house (N half gone). Greek Revival. Ca. 1846.

209: See appendix (Continuation Sheet #52)

213: concrete block; I story; flat roof; l bay. Commercial warehouse. Builders vernacular. Ca. 1976.

215: concrete block; 1 story; flat roof; 1 bay. Commercial (store, office, warehouse Builders vernacular. Ca. 1971.

219: stucco over brick; 2½-story N section with basement, 3 bays, Second Empire, slate bell-cast mansard roof with 3 6/6 light sash segmental arched dormers; boarded up windows with stone sills, plain box cornice with dentils. S section is two-story over rusticated basement with concrete block infill, 4 bays; Renaissance Revival, standing seam gable roof with wood balustrade with symmetrically turned balusters and pedestals with recessed panels; recessed window bays between pilasters, recessed panels between 2nd and 3rd floor windows, boarded up windows with stone sills; plain cornice with dentils. Corner ca. 1851; S section ca. 1900.

300 Block


301-303 (Elm Tree Row): brick (stretcher bond); 2 stories with basement; gable roof (standind seam metal); 6 bays. Two l-story, l-center-bay porches: South-2 columns with engaged rear columns, full entablature, elevated on piers, concrete steps, plain balustrades; North-2 columns with box cornice and frieze, elevated on brick piers, wood stairs on north side, porch lengthened at same time. Double house attached in row of 3 double houses. Greek Revival. Ca. 1853-54.

305-307: brick (stretcher bond); 2 stories plus high basement; gable roof (standing seam metal); 6 bays. Two 1-story, 3-bay each porches: South--square, truncated columns support simple entablature, plain rectangular balusters and rail, flat roof; open strengers and risers of wood steps with plain, rectangular newels supported on brick piers; iron fence with decorative newel posts to north of steps. North--Colonial Revival carpenter book pattern balustrade, columns and engaged columns support dentiled entablature with metal coping; supported on stone piers; wood steps with plain rectangular railing lead to it. Double house. Greek Revival. Ca. 1853-54.

United States Department of the Interior National Park Service

National Register of Historic Places Inventory—Nomination Form

Shockoe Valley and Tobacco Row Historic District, Richmond, VA Continuation sheet #46 Item number 7



Page

7. DESCRIPTION -- Inventory (continued)

NORTH 19th STREET (continued)

300 Block (continued)

309-11. (Elm Tree Row): brick (stretcher bond); 2 stories with basement; gable roof (standing seam metal); 6 bays. Two 1-story, 3-bay porches of similar Colonial Revival style elevated on brick piers with box cornice and plain frieze; decorative balustrade; 309 has reflective pilasters and wood stairs; 311 has reflective engaged columns and brick stairs. Double house. Greek Revival. Ca. 1853-54.

SOUTH 19th STREET

00 Block

8 (between E. Main and E. Cary Streets): concrete stucco on brick; 1 story; flat roof; 4 bays. Service station. Commercial vernacular (Mediterranean flavor). Ca. 1950.

24 (NW corner of S. 19th and E. Cary Streets): brick (stretcher bond); l story; flat roof; 2 bays. Parking attendants building/storage. Builders vernacular. Ca. 1950.

S. 19th between E. Cary and Dock Streets, E side: parking lot.

 γ S. 19th between E. Cary and Dock Streets, W side: scrap metal lot for Smith Iron & Metal Co., Inc.

NORTH 20th STREET

00 Block

W side N. 20th Street, S of #20 (behind Poe Shrine): vacant lot.

20: See appendix (Continuation Sheet #52)

21: brick (stretcher bond with occasional Flemish bond); 2 stories; flat roof; 5 bays. Industrial/factory. Industrial vernacular. Ca. 1915.

100 Block

110: vacant lot.

115: brick (stretcher bond and 6-course American bond); 5 stories; flat roof; 13 bays in 6 structural divisions. Industrial warehouse. Industrial vernacular/commercial whiffen. Ca. 1924.

121: brick (5-course American bond); 5 storiés; flat roof; 4 bays. Industrial. Commercial vernacular. Ca. 1904.


(See Continuation Sheet #47)

United States Department of the Interior National Park Service

National Register of Historic Places Inventory—Nomination Form

Shockoe Valley and Tobacco Row Historic District

Continuation sheet #47 Item number 7



Page

DESCRIPTION -- Inventory (continued)

NORTH 20th STREET (continued)

200 Block

232: brick (stretcher bond); 3 stories; shallow gable roof; 3 bays. 1-story, 1-side-bay (south) porch entrance portico; fluted ionic columns on granite cheek blocks; ionic entablature with dentils under cornice, plain frieze. Detached town house. Greek Revival. Ca. 1858.

SOUTH 20th STREET

00 Block

3-7: brick (5-course American bond); 2 stories; shed roof; 8 bays in 3 major divisions. Industrial. Industrial vernacular. Ca. 1930.

4-6: brick(6-course American bond); 3 stories; flat roof; 6 bays. Industrial warehouse. Industrial vernacular. Ca. 1940.

8-12: concrete, brick and glass; 7 stories with basement; flat roof; 8 structural bays. Industrial. Industrial vernacular. Ca. 1927.

W side S. 20th between E. Cary and Dock Streets: parking lot.



E side S. 20th between E. Cary and Dock Streets: vacant lot.

NORTH 21st STREET

00 Block

- 1: see sheet for 2100 E. Main Street.
- 7: brick (6-course American bond); 2 stories; shed roof; 3 bays. Detached town house. Builders vernacular. Ca. 1860.
- 9: parking lot.
- 10: brick (5-course American bond); l story; flat roof; 3 bays. Gas station. Builders commercial vernacular. Ca. 1940.
- 11-19: parking lot.
- SW corner N. 21st and E. Franklin Streets: parking lot.

100 Block

S of building at N. 21st and E. Grace Streets: American Tobacco parking lot.

United States Department of the Interior National Park Service

National Register of Historic Places Inventory—Nomination Form

Shockoe Valley and Tobacco Row Historic District, Richmond, VA

Continuation sheet #48 | Item number 7



Page

7. DESCRIPTION -- Inventory (continued)

SOUTH 21st STREET

00 Block

17: brick (7-course American with Flemish bond in N half of building; 1st, 2nd and 3rd floors of S half of building are mixed American bond with Flemish bond rows and 4th floor of S half is 6-course American bond); 4½ stories on N half of building and 4 stories on S half of building; shed roof on S half of building and gable roof of flush seam metal on N half of building; 6 bays in 2 major divisions (N & S). Warehouse and offices. Industrial vernacular. Ca. 1925.

100 Black

W side of S 21st between E. Cary and Dock Streets: vacant lot.

E side of S 21st between E. Cary and Dock Streets: parking lot.

NORTH 22nd STREET

00 Block

16-20: brick (varies from 4-7-course American bond); 3 stories; gable roof; 9 bays on 1st floor and 10 bays on 2nd/3rd floors. Industrial and warehouse. Commercial vernacular. Ca. 1870.

32: brick(6-course American bond); 3 stories; flat roof; 3 bays. Industrial. Commercial vernacular. Ca. 1910.

9-11: brick (stretcher bond); 4 stories; flat roof; 4 bays. Industrial warehouse. Commercial vernacular. Ca. 1855.

SOUTH 22nd STREET

00 Block

18 & 22 (Larus Brothers Tobacco Plant): concrete; 4 stories with basement level increasing in depth towards the S; flat roof; 7 bays. Commercial (office on 1st floor) and industrial (2nd-4th floors). Commercial vernacular (Art deco influence). Ca. 1921-25.

100 Block

 $\sim^{lpha 0}$ W side S 22nd between E Cary and Dock Streets: parking lot.

NORTH 23rd STREET

00 Block

7: brick (7-course American bond); 2 stories; shed roof; 3 bays on 1st floor and

United States Department of the Interior National Park Service

National Register of Historic Places Inventory—Nomination Form

Shockoe Valley and Tobacco Row Historic District, Richmond, VA Continuation sheet #49 Item number 7



Page

7. DESCRIPTION -- Inventory (continued)

SOUTH 23rd STREET

00 Block

- 6: brick (stretcher bond) and concrete piers and spandrals; 5 stories with basement; flat roof; 13 structural bays. Industrial. Industrial vernacular. Ca. 1926.
- 11: brick (7-course American bond with Flemish bond); 5 stories: with basement level; flat roof; 19 bays. Industrial warehouse. Industrial vernacular. Ca. 1890.

NORTH 24th STREET

1-100 Block

E side of N 24th between E Main and E Franklin Streets: parking lot.

SOUTH 24th STREET

1-100 Block

19: brick (5-course American bond); 4 stories; flat roof; 4 bays on 1st floor and 7 bays on 2nd-4th floors (5 N and 2 S). Industrial warehouse. Industrial vernacular. Ca. 1920.

E side S 24th Street: parking lot.

NORTH 25th STREET

1-100 Block

7: brick (6-course American bond); 2 stories; shed roof; 9 bays on 1st floor and 10 bays on 2nd floor. Industrial. Commercial vernacular. Ca. 1890.

SOUTH 25th STREET

1-100 Block

17: brick (5-course American bond); 12 story (clerestory); gable roof (composition); 7 bays. Industrial. Industrial vernacular. Ca. 1860.


Small building in lot between Kinney building and old American Tobacco foundry building, E side S 25th between E. Main and E. Cary Streets: brick (6-course American bond); l story; flat roof; l bay. Industrial power plant building (switch room). Industrial vernacular. Ca. 1930.

(See Continuation Sheet #50)

United States Department of the Interior National Park Service

National Register of Historic Places Inventory—Nomination Form

Shockoe Valley and Tobacco Row Historic District, Richmond, VA Continuation sheet #50 Item number 7



Page

DESCRIPTION -- Inventory (continued)

ALLEY, N SIDE OF E. GRACE STREET

W side of alley between 18th and 19th Streets: brick side and center bearing walls walls with wood front; 1 story; flat roof; 2 bays. Garage. Builders vernacular. Ca. 1920.

ALLEY BETWEEN E. MAIN AND E. FRANKLIN STREETS

√O\ E/W alley between 15th and 17th Streets: brick (6-course American bond); 1 story;
flat roof; 3 bays. Industrial. Industrial vernacular. Ca. 1895.

ALLEY BETWEEN E. MAIN AND E. CARY STREETS

N side of alley between S. 18th and S. 19th Streets: brick (6-course American bond);
4 stories; parapet roof; 4 bays. Industrial. Industrial vernacular. Ca. 1900.

A.B. CHILDREY'S ALLEY

Alley between N. 23rd and N. 24th Streets, E. Main and E. Franklin Streets: brick (5-course American bond) sides and concrete block facade; 1 story; gable roof; 2 bays. Industrial. Builders remodeling. Facade ca. 1965.

LUCKY STRIKE ALLEY

W of garage: mechanical cooling system for American Tobacco Company.

E end of Lucky Strike Alley: brick (6-course American bond); 1 story; shed roof; 9 bays. Garage. Industrial vernacular. Ca. 1930.

SE corner between Pear and 26th Streets, E. Cary and E. Main Streets: mechanical systems for American Tobacco Company Plant.

SPRUCE ALLEY

N/S alley, 1500 block, between E. Cary and E. Main Streets, S. 15th and S. 17th Streets: brick (6-course American bond); l story; 6 bays. Industrial warehouse. Industrial vernacular. Ca. 1915.


WALNUT ALLEY

Rear 1714 E. Main Street: brick (7/8-course American bond); 2 stories; flat roof; 2 bays. Outbuilding. Builders vernacular. Ca. 1880.

United States Department of the Interior National Park Service

National Register of Historic Places Inventory—Nomination Form

Shockoe Valley and Tobacco Row Historic District, Richmond, VA Continuation sheet #51 Item number 7



Page

7. DESCRIPTION -- Inventory (appendix)

EAST CARY STREET

2500 Block

2500: (Kinney Building): brick (5-course American bond -- Flemish bond row);
5 stories; flat roof; 32 bays (2nd - 4th floors) and 23 bays (1st floor). Industrial warehouse. Industrial vernacular. 1886.

EAST FRANKLIN STREET

1700 Block

1708: (Anson Richard House): brick (stretcher bond); 3 stories; gable roof (composition); 3 bays. Commercial (store with residence above). Greek Revival. Ca. 1842. Architect/builder: Anson Richards.

2000 Block

(Commercial vernacular. Ca. 1854.

MAIN STREET

1700 Block

1705: brick (stretcher bond); 3 stories; shed roof; 4 bays. Commercial (store).
Renaissance Revival. Ca. 1909. Architect: D.Wiley Anderson. Builder: A.C.
Houston.

1717-19-21: brick (stretcher bond); 2 stories; shed roof; 9 bays (2nd floor) and 10 bays (1st floor). Commercial (office on 2nd floor and store on 1st floor). Commercial vernacular. Ca. 1915. Architect: Aubrey Hunt. Builder: A.L. Hunt.

1725-29: brick (stretcher bond); 2 stories; parapet roof; 9 bays (1st floor) and 10 bays (2nd floor). Commercial (store on 1st floor and office on 2nd floor). Commercial vernacular. Ca. 1920. Architect: A.L. Hunt. Builder: S.J. Hunt & Sc

NORTH 17th STREET

00 Block

23-27: brick (stretcher bond); 2 stories; shed roof; 8 bays. Commercial (store on 1st floor and office on 2nd floor). Transitional Greek Revival/Italianate.

Ca. 1853 with altered store fronts. Builder: Mrs. James Truehart.

National Register of Historic Places Inventory—Nomination Form

Shockoe Valley and Tobacco Row Historic District, Richmond, VA Continuation sheet #52 Item number 7

For HCRS use only received date entered

Page

DESCRIPTION -- Inventory (appendix continued)

NORTH 17th STREET (continued)

300 Block

300: brick (6-course American bond); 2 stories; flat roof; 3 bays. Railroad and Industrial. Industrial RR vernacular. Ca. 1910.

NORTH 18th STREET

200 Block



211: brick (stretcher bond); 2½ stories; gable roof (standing seam metal); l pedimented dormer; 3 bays; 1-story, 3-bay porch in 2 sections: single bay Doric Greek Revival portico with awning over concrete access steps; 2 bay extension to the S with shed roof; plain, flat balusters. Detached town house. Greek Revival. Ca. 1850. Builder: John Lacy.

NORTH 19th STREET

200 Block



209: (Jewish Temple): brick (stretcher bond); 3 stories; gable roof (standing seam metal); 3 structural bays. Industrial currently; synagogue (historically). Vernacular. 1908. Builder: John Wilson.

NORTH 20th STREET

00 Block



20: brick (5-course American bond -- Flemish bond row); 4 stories; gable roof (standing seam metal); 8 bays. Industrial warehouse. Commercial Greek Revival. 1849. Architect/builder: John Enders.

EAST GRACE STREET

1800 Block



1813-15: (Crump Double House): brick (Flemish bond); 2½ stories with basement; gable roof (standing seam metal); 2 gable dormers; 6 bays. Double house. Federal. 1818.

EAST MAIN STREET

1500 Block

1557: brick (stretcher bond); 3½ stories; shed roof; 3 bays. Commercial (store). Commercial Vernacular. Ca. 1890.

